

# GENERAL NOTES

1. THE GENERAL CONTRACTOR AND EACH SUBCONTRACTOR SHALL VERIFY ALL DIMENSIONS AND SITE CONDITIONS BEFORE STARTING WORK. THE ARCHITECT OR **ES/IFME, INC.** SHALL BE NOTIFIED OF ANY DISCREPANCY.
2. DIMENSIONING SHALL TAKE PRECEDENCE OVER SCALES SHOWN ON DRAWINGS. TYPICAL DETAILS AND GENERAL NOTES ARE MADE AND COARSE AGGREGATE SHALL BE USED WHEN CONDITIONS ARE NOT SHOWN OTHERWISE.
3. NOTES AND DETAILS ON DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS, WHERE NO CONTRADICTORY STANDARDS LISTED IN THESE NOTES AND SPECIFICATIONS.
4. APPROVAL BY THE INSPECTOR DOES NOT MEAN APPROVAL OR ALLOWABLE FAILURE TO COMPLY WITH THE PLANS AND SPECIFICATIONS. ANY DESIGN WHICH FAILS TO BE CLEAR OR IS AMBIGUOUS MUST BE REFERRED TO THE DESIGNER OR ENGINEER FOR INTERPRETATION OR CLARIFICATION.
5. SEE ARCHITECTURAL, ELECTRICAL AND MECHANICAL DRAWINGS FOR PITS, TRENCHES, ROOF OPENINGS, DEPRESSIONS ETC. NOT SHOWN ON STRUCTURAL DRAWINGS.
6. VIBRATION EFFECTS OF MECHANICAL EQUIPMENT HAVE NOT BEEN CONSIDERED BY **ES/IFME, INC.**
7. ALL REINFORCING BARS SHALL BE ACCURATELY AND SECURELY PLACED BEFORE POURING CONCRETE.
8. CONCRETE PROTECTION FOR REINFORCEMENT SHALL BE AS FOLLOWS:
  - A. EQUAL TO THE DIAMETER OF THE BARS. COVER SHALL BE AS FOLLOWS:
 

CONC. MASONRY	3"	2"
A. Poured Against Earth	3"	2"
B. Poured Against Form Below Grade	2"	2"
#6 and Larger	2"	2"
#5 and Smaller	1 1/2"	1 1/2"
  - C. FORMED SLABS
  - D. SLABS ON GRADE (FROM TOP OF SLAB)
  - E. COLUMNS AND BEAMS TO MAIN BARS
  - F. WALLS - EXPOSED TO WEATHER
9. NOT EXPOSED TO WEATHER, #11 and SMALLER
10. #14 and #18
9. CONTRACTOR SHALL INVESTIGATE SITE DURING CLEARING AND EXCAVATION OPERATIONS FOR FILLED EXCAVATIONS OR BURIED STRUCTURES SUCH AS CESSPOOLS, CISTERNS, FOUNDATIONS, ETC. IF ANY SUCH STRUCTURES ARE FOUND, **ES/IFME, INC.** AND THE SOIL ENGINEER, EXCAVATION AND COMPACTION SHALL BE DONE UNDER THE SUPERVISION OF THE SOIL ENGINEER.
10. CONSTRUCTION MATERIALS SHALL BE SPREAD OUT IF PLACED ON FRAMED FLOORS OR ROOF. LOAD SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. PROVIDE ADEQUATE SURFACE WATER WILL DRAIN AWAY FROM BUILDING. DRAINAGE SHALL BE 2% FROM BUILDING TO SWALE LINE. SWALE SHALL DRAIN AT 1% (MIN.) FROM REAR OF BUILDING TO STREET.
11. THERE SHALL BE NO UTILITY TRENCH NEAR THE BUILDING FOUNDATION WHICH EXTEND DEEPER THAN 45 DEGREE LINE PROJECTED DOWN AND AWAY FROM THE BOTTOM OUTSIDE CORNER OF ANY FOOTING.
12. SLAB SUBGRADE REQUIREMENTS ARE NOT WITHIN THE SCOPE OF WORK OR LIABILITY OF **ES/IFME, INC.** THE SUBGRADE CONFIGURATION SHOWN IN DETAIL 1/01 OR THE POST-TENSION DETAILS REFLECT THE GENERAL RECOMMENDATIONS OF THE SOILS ENGINEER, AND/OR THE SITE CONDITIONS. IT IS THE RESPONSIBILITY OF THE OWNER TO REVIEW THE SLAB SUBGRADE CONFIGURATION WITH THE SOILS ENGINEER, AND CONCRETE/FLOORING CONTRACTORS, FOR ADEQUATE MOISTURE PROTECTION. PLEASE REFER TO THE SOILS REPORT FOR ADDITIONAL RECOMMENDATIONS.
13. ALL HOLDOWN ANCHORS, POST BASES AND HOLDOWN BOLTS SHALL BE TIED INTO PLACE PRIOR TO FOUNDATION INSPECTION.
14. REBAR 20"-0" REBAR IN FOUNDATION AT SERVICE LOCATIONS. STUB UP REBAR ABOVE THE FLOOR BY ELECTRIC SERVICE METERS.
15. FOR THE LOCATION OF CONTROL JOISTS, REFER TO THE FOUNDATION PLAN. (ZIP STRIP OR EQUAL) MINIMUM OF 20"-0" O.C. EACH WAY IS RECOMMENDED.
16. DRIVEWAY PAVING SHALL BE 4" PORTLAND CEMENT CONCRETE (5 SACKS MIN.).
17. FOR POST-TENSION SLAB, REFER TO APPROVED PLANS PREPARED BY OTHERS.
18. MINIMUM SLAB REINFORCEMENT AND PAD REQUIREMENT SHALL CONFORM TO THE SOILS ENGINEER'S RECOMMENDATIONS, U.N.O.

# REINFORCING STEEL

1. ALL REINFORCING SHALL BE ASTM A-615 GRADE 40 FOR #4 BARS AND SMALLER. ALL REINFORCING SHALL BE ASTM A-615 GRADE 60 FOR #5 BARS AND LARGER. WELDED WIRE FABRIC TO BE ASTM A-185, LAP 1-1/2" SPACES, 9" MIN. FOR STRUCTURAL SLABS ALL REINFORCING #5 AND LARGER TO BE ASTM A-615 GRADE 60.
2. ALL BARS SHALL BE DEFORMED AS PER ASTM A615 / A615M.
3. ALL BARS SHALL BE CLEAN OF LOOSE FLAKY RUST, GREASE OR OIL AND BENDS SHALL BE MADE COLD.
4. SPLICING OF #3-#5 BARS SHALL HAVE A MIN. LAPPING OF 42 DIA. OR 32" MIN., WHICH EVER IS GREATER, IN ALL CONTINUOUS REINFORCEMENT OF FOOTINGS AND CONCRETE WALLS, EXCEPT AS NOTED ON PLANS. MASONRY REINFORCEMENT SHALL HAVE LAPPINGS OF 40 DIA. FOR GRADE 40 & 48 DIA. FOR GRADE 60 MIN. OR 2'-0", WHICH EVER IS GREATER.
6. ALL REINFORCING SHALL BE ACCURATELY AND SECURELY PLACED BEFORE POURING CONCRETE.
7. CONCRETE PROTECTION FOR REINFORCEMENT SHALL BE AS FOLLOWS:
  - A. EQUAL TO THE DIAMETER OF THE BARS. COVER SHALL BE AS FOLLOWS:
 

CONC. MASONRY	3"	2"
A. Poured Against Earth	3"	2"
B. Poured Against Form Below Grade	2"	2"
#6 and Larger	2"	2"
#5 and Smaller	1 1/2"	1 1/2"
  - C. FORMED SLABS
  - D. SLABS ON GRADE (FROM TOP OF SLAB)
  - E. COLUMNS AND BEAMS TO MAIN BARS
  - F. WALLS - EXPOSED TO WEATHER
8. NOT EXPOSED TO WEATHER, #11 and SMALLER
9. #14 and #18

# WOOD TRUSSES

1. MANUFACTURER SHALL SUPPLY TO THE ARCHITECT/ENGINEER AND THE BUILDING DEPARTMENT, CALCULATIONS AND SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION. ALL CALCULATIONS AND SHOP DRAWINGS SHALL BE SIGNED BY A CALIFORNIA REGISTERED PROFESSIONAL ENGINEER. IT SHALL BE THE RESPONSIBILITY OF THE MANUFACTURER TO OBTAIN BUILDING DEPARTMENT APPROVAL FOR CALCULATIONS AND SHOP DRAWINGS PRIOR TO FABRICATION.
2. TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST LOCAL BUILDING CODE FOR ALL LOADS IMPOSED, INCLUDING LATERAL LOADS AND MECHANICAL EQUIPMENT LOADS.
3. ALL CONNECTORS SHALL BE ICC APPROVED AND OF ADEQUATE STRENGTH TO RESIST STRESSES DUE TO THE LOADINGS INVOLVED.
4. TOTAL LOAD DEFLECTIONS SHALL BE LIMITED TO L/240
5. CROSS BRIDGING AND/OR BRACING SHALL BE PROVIDED AND DETAIL AS REQUIRED TO ADEQUATELY BRACE ALL TRUSSES.
6. EACH TRUSS SHALL BE LEGIBLY BRANDED, MARKED OR OTHERWISE HAVE PERMANENTLY AFFIXED THERETO THE FOLLOWING INFORMATION LOCATED WITHIN 2 FEET OF THE CENTER OF THE SPAN ON THE FACE OF THE BOTTOM CHORD:
  - a) IDENTIFY OF THE COMPANY MANUFACTURING THE TRUSS
  - b) THE DESIGN LOAD
  - c) THE SPACING OF THE TRUSSES
  - d) DOUGLAS FIR SPECIES TO BE USED FOR TOP AND BOTTOM CHORDS OF TRUSSES U.N.O.

# STRUCTURAL OBSERVATION REQ.

1. STRUCTURAL OBSERVATIONS SHALL BE PROVIDED IN ACCORDANCE WITH SECTION 1709 OF THE CALIFORNIA BUILDING CODE FOR THIS PROJECT. STRUCTURAL OBSERVATION IS DEFINED IN CBC SECTION 1702 AS "...THE VISUAL OBSERVATION OF THE STRUCTURAL SYSTEM FOR GENERAL CONFORMANCE TO THE APPROVED PLANS AND SPECIFICATIONS AT SIGNIFICANT CONSTRUCTION STAGES AND AT COMPLETION OF THE STRUCTURAL SYSTEM..."
2. STRUCTURAL OBSERVATION SHALL BE PERFORMED BY THE ENGINEER RESPONSIBLE FOR THE DESIGN OF THE STRUCTURAL SYSTEM, OR BY AN OBSERVER DESIGNATED BY THE ENGINEER OF RECORD. THE STRUCTURAL OBSERVER SHALL BE EMPLOYED BY THE **ES/IFME, INC.** NOT THE CONTRACTOR.
3. REQUIRED OBSERVATION: SINGLE FAMILY=MODELS / MULTI-FAMILY=ALL UNITS A. FOUNDATION (MULTI-FAMILY ONLY) B. COMPLETE FRAMING PRIOR TO WRAPPING

# CONTRACTOR RESPONSIBILITY

CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A WIND OR SEISMIC FORCE RESISTING SYSTEM/COMPONENT LISTED IN THE "STATEMENT OF SPECIAL INSPECTION" SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING INSPECTORS AND THE OWNER PRIOR TO COMMENCEMENT OF WORK ON SUCH SYSTEM OR COMPONENT PER SECTION 1709.

# CORROSION REQUIREMENTS

CAT.	SEVERITY CLASS	CONDITION	NORMAL WT AGGREGATE (lb/cu yd)	WGT. CONC. (MIN. %) (lb/cu yd)	MINIMUM WGT OF AGGREGATE (lb/cu yd)	ADDITIONAL REQUIREMENTS
S SULFATE	NOT APPLICABLE	S0	0-0.10	0-150	N/A	2,500
	MODERATE	S1	0.10-0.20	150-1500	0.50	4,000
	SEVERE	S2	0.20-2.00	1500-10,000	0.45	4,500
	VERY SEVERE	S3	>2.00	>10,000	0.45	4,500
C CORROSION PROTECTION OF REINFORCEMENT	NOT APPLICABLE	C0	CONCRETE DRY OR PROTECTED FROM MOISTURE	N/A	2,500	1.00
	MODERATE	C1	CONCRETE EXPOSED TO MOISTURE BUT NOT TO EXTERNAL SOURCES OF CHLORIDES.	N/A	2,500	0.30
	SEVERE **	C2	CONCRETE EXPOSED TO MOISTURE AND EXTERNAL SOURCES OF CHLORIDES FROM DEICING CHEMICALS, WATER, SEAWATER, OR SPRAY FROM THESE SOURCES.	.40	5,000	0.15

f Alternative combinations of cementitious materials of those listed in Table 4.3.1 shall be permitted when tested for sulfate resistance and meeting criteria in 4.5.1 of ACI 318.  
 † For seawater exposure, other types of portland cements with tricalcium aluminate (C<sub>3</sub>A) contents up to 10 percent are permitted if the w/c does not exceed 0.40.  
 § Other available types of cement such as Type III or Type I are permitted in Exposure Classes S1 or S2 if the C<sub>3</sub>A contents are less than 8 or 5 percent, respectively.  
 ¶ The amount of the specific source of the pozzolan or slag to be used shall not be less than the amount that has been determined by service record to improve sulfate resistance when used in concrete containing Type V cement. Alternatively, the amount of the specific source of the pozzolan or slag to be used shall not be less than the amount listed in accordance with ASTM C1012 and meeting the criteria of 4.5.1 of ACI 318.  
 \*\* Water-soluble chloride ion content that is contributed from the ingredients includes water, aggregates, cementitious materials, and admixtures shall be determined on the concrete mixture by ASTM C1218 at age between 23 and 42 days.  
 †† Requirements of 7.7.6 of ACI 318 shall be satisfied. See 18.16 of ACI 318 for unbonded tendons.

# CONCRETE

1. ALL CONCRETE SHALL CONFORM TO THE LATEST EDITION OF THE CALIFORNIA BUILDING CODE.
2. CONCRETE SHALL BE DESIGNED AND TESTED AS OUTLINED IN THE SPECS.
3. ALL CEMENT SHALL CONFORM TO ASTM C-150, PLEASE CROSS-REFERENCE EXPOSURE CLASS SHOWN BELOW WITH CORROSION TABLE ON SGN-2 FOR CONCRETE REQUIREMENTS
4. FINE AND COARSE AGGREGATE SHALL CONFORM TO ASTM C-33 FOR STANDARD WEIGHT CONCRETE AND ASTM C-330 FOR LIGHT WEIGHT CONCRETE.
5. ALL AGGREGATE SHALL BE COMPARABLE TO "SAN GABRIEL VALLEY" AGGREGATE. THE SHRINKAGE SHALL BE AS PER ASTM C-157 WITH THE AVERAGE DRYING SHRINKAGE AT 28-DAYS NOT EXCEEDING 0.05%.
6. DRYPACK SHALL BE COMPOSED OF ONE PART PORTLAND CEMENT TO NOT MORE THAN THREE PARTS SAND.
7. ANCHOR BOLTS, HOLDOWN BOLTS, DOWELS, INSERTS, ETC. SHALL BE SECURELY TIED IN PLACE PRIOR TO POURING CONCRETE.
8. CONCRETE SHALL BE CURED BY KEEPING CONTINUOUSLY WET FOR 10-DAYS OR BY AN APPROVED CURING COMPOUND.
9. REFER TO ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS FOR MISCELLANEOUS ITEMS TO BE CAST INTO CONCRETE AND FLOOR DEPRESSIONS, PITS, ETC.
10. SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS OF EXPANSION JOINTS, SCORING, ETC. FOR CONCRETE WALKS AND SLABS.
11. ALL STRUCTURAL CONCRETE, TYPE II OR V  $F_c = 3,000$  PSI ALL SLAB-ON-GRADE, TYPE II OR V  $F_c = 2,500$  PSI ALL CONTINUOUS FOOTINGS AND WALLS, TYPE II OR V  $F_c = 2,500$  PSI ALL CONCRETE SHALL REACH MINIMUM COMPRESSIVE STRENGTH 28 - DAYS.
12. ALL CONCRETE WITH  $F_c$  GREATER THAN 2,500 PSI SHALL HAVE SPECIAL INSPECTION PER SECTION 1704 OF THE LATEST CBC UNLESS NOTED OTHERWISE.
13. CONCRETE FOR SLAB ON GRADE SHALL HAVE A MAXIMUM OF 5 in. OF SLUMP PER ASTM C-143. 5 SACKS OF CEMENT PER CUBIC YARD OF CONCRETE. CEMENT ASTM C-150 TYPE 1 OR 2 MIN.
14. CONCRETE MIX IS TO ADDRESS BLEEDING, SHRINKAGE AND CURLING PER ACI 302-0R-06.

# FOUNDATION/SITWORK

1. THE FOUNDATION DESIGN IS BASED ON THE FOUNDATION INVESTIGATION BY SOIL REPORT SUBMITTED:
  - PER: CORNERSTONE
  - PROJECT NO.: 230-1-5
  - DATE: 10-30-15
2. THE ALLOWABLE SOIL BEARING VALUE IS 1500 PSF FOR CONTINUOUS FOOTINGS, UNLESS NOTED OTHERWISE IN THE DESIGN LOADS BELOW.
3. ALL SITE PREPARATION, EXCAVATION AND COMPACTION SHALL BE DONE UNDER THE SUPERVISION OF THE SOIL ENGINEER.
4. SEPARATE PERMITS SHALL BE OBTAINED FOR ALL FENCES AND WALLS, AS REQUIRED.
5. PROVIDE NON-EXPANSIVE FILL AS REQUIRED TO LEVEL PAD.
6. SURFACE WATER WILL DRAIN AWAY FROM BUILDING. DRAINAGE SHALL BE 2% FROM BUILDING TO SWALE LINE. SWALE SHALL DRAIN AT 1% (MIN.) FROM REAR OF BUILDING TO STREET.
7. THERE SHALL BE NO UTILITY TRENCH NEAR THE BUILDING FOUNDATION WHICH EXTEND DEEPER THAN 45 DEGREE LINE PROJECTED DOWN AND AWAY FROM THE BOTTOM OUTSIDE CORNER OF ANY FOOTING.
8. SLAB SUBGRADE REQUIREMENTS ARE NOT WITHIN THE SCOPE OF WORK OR LIABILITY OF **ES/IFME, INC.** THE SUBGRADE CONFIGURATION SHOWN IN DETAIL 1/01 OR THE POST-TENSION DETAILS REFLECT THE GENERAL RECOMMENDATIONS OF THE SOILS ENGINEER, AND/OR THE SITE CONDITIONS. IT IS THE RESPONSIBILITY OF THE OWNER TO REVIEW THE SLAB SUBGRADE CONFIGURATION WITH THE SOILS ENGINEER, AND CONCRETE/FLOORING CONTRACTORS, FOR ADEQUATE MOISTURE PROTECTION. PLEASE REFER TO THE SOILS REPORT FOR ADDITIONAL RECOMMENDATIONS.
9. ALL HOLDOWN ANCHORS, POST BASES AND HOLDOWN BOLTS SHALL BE TIED INTO PLACE PRIOR TO FOUNDATION INSPECTION.
10. REBAR 20"-0" REBAR IN FOUNDATION AT SERVICE LOCATIONS. STUB UP REBAR ABOVE THE FLOOR BY ELECTRIC SERVICE METERS.
11. FOR THE LOCATION OF CONTROL JOISTS, REFER TO THE FOUNDATION PLAN. (ZIP STRIP OR EQUAL) MINIMUM OF 20"-0" O.C. EACH WAY IS RECOMMENDED.
12. DRIVEWAY PAVING SHALL BE 4" PORTLAND CEMENT CONCRETE (5 SACKS MIN.).
13. FOR POST-TENSION SLAB, REFER TO APPROVED PLANS PREPARED BY OTHERS.
14. MINIMUM SLAB REINFORCEMENT AND PAD REQUIREMENT SHALL CONFORM TO THE SOILS ENGINEER'S RECOMMENDATIONS, U.N.O.

# DESIGN LOADS:

VERTICAL	SEISMIC	WIND
ROOF DL = 20 PSF	SEISMIC DESIGN CATEGORY=D	WIND VELOCITY = 110 MPH
ROOF LL = 20 PSF	SITE CLASS = C	WIND EXPOSURE = C
FLOOR DL = 14 PSF	BASIC-SEISMIC-FORCE-RESISTING SYSTEM LIGHT FRAMED WALLS	
FLOOR LL = 40 PSF	ANALYSIS PROCEDURE EQUIVALENT FORCE METHOD	
	$I_e = 1$	$R = 6.5$
	(PER USGS WEBSITE) $S_s = 2.563$	$S_1 =$
	(PER USGS WEBSITE) $F_a = 1.0$	(PER USGS WEBSITE) $F_v = 1.3$
	(FOR UNIFORM DESIGN) $S_{ds} = 1.709$	$V = 0.239$ W

TRUSS DESIGN: UNINHABITABLE ATTICS WHICH QUALIFY FOR LIMITED STORAGE  
 ALL GLUED LAMINATED BEAMS WILL BE DESIGNED WITH LL=20 PSF AND BOTTOM CHORD DL=10 PSF PER TABLE 1607.1.

# GLULAMS/MFR. WD. PROD.

1. ALL GLUED LAMINATED MEMBERS SHALL BE MADE OF 1-1/2" DOUGLAS FIR LAMINATIONS, COMBINATION 24-F PER AITC.
2. IND. APP. GRADE:  $F_b=2400$  PSI,  $F_v=240$  PSI,  $E=1.81 \times 10^6$  PSI
3. INDUSTRIAL APPEARANCE GRADE SHALL BE USED, WITH MOISTURE CONTENT BETWEEN 7 - 14 PERCENT, UNLESS NOTED OTHERWISE.
4. FABRICATOR SHALL BE A MEMBER OF AITC AND ALL FABRICATION SHALL BE PERFORMED IN ACCORDANCE WITH AITC A190.1 & ASTM 3737. LUMBER SHALL BE MARKED WITH AN AITC QUALITY MARK INDICATING CONFORMANCE WITH THE COMMERCIAL STANDARD "STRUCTURAL GLUED LAMINATED LUMBER"
5. GLUED LAMINATED MEMBERS SHALL BE ACCOMPANIED BY A CERTIFICATE OF INSPECTION. CONTRACTOR SHALL BEAR EXPENSES OF INSPECTION AND TESTS. A CERTIFICATE OF INSPECTION SHALL BE SUBMITTED TO THE BUILDING DEPARTMENT.
6. THE FABRICATOR SHALL SUBMIT COMPLETE SHOP DRAWINGS TO BUILDING DEPARTMENT AND **ES/IFME, INC.** FOR APPROVAL PRIOR TO FABRICATION.
7. ALL GLUED LAMINATED BEAMS WILL HAVE A STANDARD CAMBER BASED ON A RADIUS=1600 UNLESS NOTED OTHERWISE.
8. PARALLAM PSL 2.0E BY I-LEVEL PER ESR-1387
9.  $f_b=2900$  PSI;  $f_v=290$  PSI;  $E=2.0 \times 10^6$  PSI -  $RR\#$  25202
10. TIMBERSTRAND LSL 1.55E BY I-LEVEL PER ESR-1387
11.  $f_b=2325$  PSI;  $f_v=310$  PSI;  $E=1.55 \times 10^6$  PSI -  $RR\#$  25202
12. VERKAS-LAM PSL 2.0 E BY BOISE CASCADE PER ICC ESR-1057
13. ESR-1040  $f_b=3100$  PSI;  $f_v=285$  PSI;  $E=2.0 \times 10^6$  PSI
14. RIDIGLAM LVL 2.0E BY ROSEBURG PER ICC ESR-1210
15.  $f_b=2900$  PSI;  $f_v=285$  PSI;  $E=2.0 \times 10^6$  PSI  $RR\#$  25439
16. RIDIGLAM LVL 1.5E BY ROSEBURG PER ICC ESR-1210
17.  $f_b=2400$  PSI;  $f_v=220$  PSI;  $E=1.5 \times 10^6$  PSI  $RR\#$  25439
18. GLULAM (V4) BY BOISE CASCADE PER ANS/AITC A190.10
19.  $f_b=2400$  PSI;  $f_v=285$  PSI;  $E=1.8 \times 10^6$  PSI
20. PROVIDE MULTIPLE 2x4 SQUASH BLOCKS UNDER BEARING POINT LOAD FROM ABOVE TO TOP PLATES BELOW AT FLOOR LEVEL.
21. I-LEVEL I-JOISTS PER ICC ESR#1533, RR#25538 LOUISIANA PACIFIC I-JOISTS PER ICC ESR#1130, RR#25176 BOISE CASCADE I-JOISTS PER ICC ESR#1336, RR#24999 ROSEBURG I-JOISTS PER ICC ESR#1251, RR#25439
22. PROVIDE DOUBLE I-JOISTS OR DOUBLE I-JOIST BLOCKS WHEN 16d SOLE PLATE NAILING IS LESS THAN 4" O.C. AT SHEAR WALL JOINT.
23. REFER TO I-JOIST MANUFACTURER SPECIFICATION FOR DRILLING OF HOLES THRU I-JOIST WEB.

# LUMBER/CARPENTRY

1. ALL STRUCTURAL LUMBER SHALL BE GRADED IN ACCORDANCE WITH THE AMERICAN SOFTWOOD LUMBER STANDARD DOC PS 20.
2. ALL WOOD BEARING ON CONCRETE OR MASONRY SHALL BE PRESSURE TREATED DOUG FIR OR REDWOOD WITH SODIUM BORATE (SBX) OR DISODIUM OCTABORATE TETRAHYDRATE (DOT).
3. FINE AND COARSE AGGREGATE SHALL BE BORED WITH A BIT 1/32" TO 1/16" LARGER THAN THE NOMINAL BOLT DIAMETER.
4. ALL BOLTS SHALL BE RE-TIGHTENED PRIOR TO APPLICATION OF PLYWOOD, PLASTER, ETC.
5. STRUCTURAL MEMBERS SHALL NOT BE CUT FOR PIPES, ETC. UNLESS SPECIFICALLY NOTED OR DETAILED.
6. 2X SOLID BLOCKING SHALL BE PLACED BETWEEN JOISTS OR RAFTERS AT ALL SUPPORTS, EXCEPT WHEN LEDGERED.
7. CROSS-BRIDGING SHALL BE PROVIDED AT 8'-0" O.C. MAX. FOR ALL FLOOR JOISTS OVER 10' IN DEPTH AND ALL ROOF JOISTS OVER 10' DEPTH. USE SOLID BLOCKING OR AT LEAST TYPE METAL BRIDGING, WHERE STATED IN PRODUCTS ICC REPORT. CROSS-BRIDGING IS NOT REQUIRED FOR PRE-FABRICATED I-JOISTS.
8. ALL STRUCTURAL PLYWOOD SHALL BE STRUCTURAL II OR C-D GRADE WITH EXTERIOR GLUE UNLESS NOTED OTHERWISE AND CONFORM TO DOC PS1 OR PS2. EACH SHEET SHALL BE IDENTIFIED BY A REGISTERED STAMP D.F.P.A OR A.P.A.
9. ALL BOLTS BEARING ON WOOD SHALL HAVE STANDARD CUT WASHERS UNDER HEAD AND NUT UNLESS NOTED OTHERWISE.
10. ALL METAL ANCHORS, FASTENERS AND CONNECTORS ETC. SHALL BE FROM SIMPSON STRONG-TIE (S.T.M.). SUBSTITUTIONS MUST BE PRE-APPROVED IN WRITING BY **ES/IFME, INC.**
11. ALL STRUCTURAL LUMBER SHALL BE DOUGLAS FIR-LARCH, 19% MAX. MOISTURE CONTENT, OF THE FOLLOWING GRADES UNLESS NOTED OTHERWISE:
  - 2X4 STUDS (UP TO 10') "STUD" OR BETTER
  - 2X4 STUDS (OVER 10') "NO.2" OR BETTER
  - 2X PLATES & 3X PLATES "STANDARD" OR BETTER
  - 2X6 STUDS NO.2
  - 2X JOIST NO.2
  - 4X10 POST AND SMALLER NO.2 OR STANDARD
  - 4X12 POST AND LARGER NO.1
  - BEAMS AND STRINGERS NO.2
  - 4X12 AND SMALLER NO.1
  - 4X12 AND LARGER NO.1
  - 6X AND 8X NO.1
  - POST/TIMBERS NO.1
12. ROOF PLANKING AND DECKING, COMDEX BOARD SHTG. AND STRIPPING, SUITABLE FOR INTENDED USE. 2012 NDS STRESS VALUES FOR DOUGLAS FIR-LARCH:
 

2X4 #2:	Fb=1350/1552	Fv=180	psi	E=1.6x10 <sup>6</sup>
2X6 #2:	Fb=1170/1345	PSI		
2X8 #2:	Fb=1080/1242	PSI		
2X10 #2:	Fb=990/1138	PSI		
2X12 #2:	Fb=900/1150	PSI		
2X14 #2:	Fb=810/931	PSI		
4X4 #2:	Fb=1350	PSI		
4X6 #2:	Fb=1170	PSI		
4X8 #2:	Fb=1170	PSI		
4X10 #2:	Fb=1080	PSI		
4X12 #1:	Fb=1100	PSI		
4X14 #1:	Fb=1000	PSI		
4X16 #1:	Fb=1000	PSI		
6X10 #1:	Fb=1350	PSI		
6X12 #1:	Fb=1350	PSI		
13. ALL NAILING TO BE PER TABLE NUMBER 2304.9.1 OF THE LATEST CALIFORNIA BUILDING CODE, UNLESS NOTED OTHERWISE.
14. PLYWOOD FLOOR AND ROOF SHEATHING SHALL BE LAID CONTINUOUS OVER TWO OR MORE SUPPORTS WITH FACE GRAIN PERPENDICULAR TO SUPPORTS (UNLESS SHOWN OTHERWISE). STAGGER ALL PLYWOOD PANELS A MINIMUM OF 4'-0".
15. EXTERIOR WALLS SHALL BE ADJACENT TO WOOD MEMBER IN TRUSSES IS REQUIRED, THE LATERAL BRACE MUST END ON AN EXTERIOR BEARING WALL.
16. FRAMING CONTRACTOR SHALL PROVIDE BACKING AS REQUIRED FOR ALL LIGHT FIXTURES, CABINETS, WARDROBES, AND HANDRAILS AS REQUIRED AND REQUESTED BY GENERAL CONTRACTOR.
17. EXTERIOR WOOD POSTS AND COLUMNS SUPPORTED BY A CONCRETE SLAB SHALL BE INSTALLED A MINIMUM OF 8" ABOVE EXPOSED EARTH AND AT LEAST 1" ABOVE SLAB ON METAL POST BASES. EXCEPT: POSTS OR COLUMNS OF APPROVED WOOD WITH NATURAL RESISTANCE TO DECAY OR TREATED WOOD. POSTS OR COLUMNS RESTING ON CONCRETE PIERS SURROUNDED BY EXISTING GRADE SHALL BE A MINIMUM OF 8" ABOVE ADJACENT GRADE PER C.B.C. SECT. 2304.11.2.2 ALL ISOLATED INTERIOR AND EXTERIOR WOOD POSTS ATTACHED DIRECTLY TO CONCRETE SHALL BE SECURED WITH SIMPSON "PB" OR EQUIVALENT.
18. PROVIDE 2x4 FLAT HEADERS AT ALL INTERIOR NON-BEARING OPENINGS UP TO 36 INCHES IN WIDTH AND 4x4 HEADERS FOR OPENINGS 3' TO 6 FEET IN WIDTH.
19. PROVIDE MINIMUM 1/2" CLEARANCE (VOID SPACE) FROM TOP OF ALL INTERIOR NON-BEARING PARTITIONS TO ROOF AND CEILING FRAMING ABOVE.
20. ALL EXTERIOR WALLS ADJACENT TO WALLS TO BE BUILT SHALL BE BALLOON FRAMED WITH CONTINUOUS STUDS TO BOTTOM CHORD OF TRUSS OR RAFTER, U.N.O.
21. WHEN PLYWOOD SIDING IS USED AS AN EXTERIOR OR INTERIOR WALL COVERING, PROVIDE SOLID BLOCKING AT ALL ENDS OF SIDING BETWEEN SOLE PLATE AND TOP PLATE. "Z" BAR METAL SHALL BE USED AT EXTERIOR HORIZONTAL JOINTS.
22. INSTALL FIREBLOCKS TO CUT OFF ALL HORIZONTAL AND VERTICAL DRAFT OPENINGS BETWEEN TWO STORES AND BETWEEN STORES AND ATTIC. FIREBLOCKS SHALL BE OF 2 INCH NOMINAL THICKNESS. LOCATION OF FIREBLOCKS SHALL INCLUDE:
  - A. STUD WALLS AT FURRED SOFFITS, CEILING AND FLOOR LEVELS.
  - B. AROUND TOP, BOTTOM, SIDES AND ENDS OF SLIDING POCKET DOORS
  - C. BETWEEN STAIR STRINGERS AT TOP AND BOTTOM OF RUN AND BETWEEN STUDS IN A WALL PARALLEL AND ADJOINING RUN OF STAIRS.
23. FASTENING OF MULTIPLE MEMBERS: DOUBLE & TRIPLE JOISTS: 16d NAILS AT 12" O.C. STAGGERED (BOTH SIDES FOR TRIPLES). FOUR OR MORE JOISTS: 1/2" DIA. M.B's AT 18" O.C. STAGGERED. 4X OR LARGER BEAMS; 1/2" DIA. M.B's AT 12" O.C. STAGGERED.
24. ALL ROUNG OR RESAWN BEAMS ARE TO BE FREE OF GRADING STAMP LABELS AND FREE OF HEART CENTER.
25. ALL HUNG JOISTS SHALL BE HUNG WITH SIMPSON "LUS" HANGERS U.N.O., AND SIMPSON "IUS" FOR I/J's, U.N.O.
26. ALL BEARING WALLS ON A WOOD FLOOR ARE TO BE SUPPORTED WITH DOUBLE JOISTS OR SOLID BLOCKING UNLESS NOTED OTHERWISE.
27. ROOF SHEATHING IS TO CONTINUE UNDER CALIFORNIA FRAMING, TYP.
28. APPLY SHEAR WALL PLYWOOD PRIOR TO ALL BOX-OUTS, FUR-OUTS, ETC.
29. PROVIDE FURRING AS NEEDED TO ALIGN NON-SHEAR WALLS WITH SHEAR WALLS.
30. PROVIDE 4X OR DOUBLE 2X MEMBERS UNDER SOLE PLATE NAILING LESS THAN 16" O.C.
31. DOUBLE TOP PLATES w/MIN. 48 in. LAP SPLICES TO BE PROVIDED w/MIN (8) 16d's PER TOP PLATE SPLICE.
32. TOP PLATE BREAKS AND SPLICES SHALL OCCUR OVER A STUD OR POST.
33. SOLID BLOCKING BETWEEN PERPENDICULAR JOIST AT BEARING AND AT SHEAR WALLS.
34. ALL EXPOSED BEAMS AND HEAVY TIMBER RECOMMENDED TO BE FREE OF HEART CENTER.
35. ALL ISOLATED POSTS AND BEAMS TO HAVE SIMPSON PB'S AND/OR BC'S MINIMUM, UNLESS NOTED OTHERWISE.
36. ALL SIMPSON HD, HTT, HDQ, HDU, PHD, HDA, AND CB HOLDOWNS TO BE FASTENED TO 1/4" DIA. POST MIN. U.N.O.
37. ALL EXTERIOR WALLS ARE TO BE SECURED WITH MIN. 1/2" DIA. x 10" ANCHOR BOLTS AT 72 in. O.C., U.N.O.
38. ALL INTERIOR WALLS ARE TO BE SECURED WITH ANCHOR PINS PER MANUFACTURER'S RECOMMENDATION, U.N.O. CALCULATIONS GIVEN IN ALL CASES. RECOMMENDED SIMPSON .145" DIA. PDP POWER ACTUATED HANGERS 3" LONG @ 24" o.c. U.N.O. (ICC ESR#2138) OR EQUAL.
39. ALL CONVENTIONAL FRAME PORTIONS OF STRUCTURE ARE TO BE CONSTRUCTED PER SECTION 2308 OF THE CALIFORNIA BUILDING CODE, U.N.O.
40. ALL SHOP DRAWINGS ARE TO BE REVIEWED BY THE CONTRACTOR AND THE ARCHITECT PRIOR TO SUBMITTAL FOR ENGINEER REVIEW.
41. TRUSS MANUFACTURER TO PROVIDE CALCULATIONS, SHOP DRAWINGS, DETAILS, TRUSS HANGERS, BRIDGING AND ERECTION BRACING.
42. PROVIDE DOUBLE 2X SOLE PLATES WITH SOLE PLATE NAILING AS SPECIFIED ON THE PLANS AT BOTH PLATES WHERE 1 1/2" LIGHT WEIGHT CONCRETE IS USED AT THE FLOOR.
43. WHERE BOTH TOP PLATES ARE BROKEN, STRAP WITH ST6224 MIN. U.N.O.
44. COMMON NAILS SHALL BE USED FOR ALL PLY SHEATHING TOP PLATE SPLICES. BOX NAILS MAY BE USED AT SOLE PLATE NAILING. ALL HARDWARE SHALL BE INSTALLED WITH NAILS PER THE MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS.
45. ALL HEADERS SHALL BE FRAMED WITH A MINIMUM OF (1) 2X4 TRIMMER AND (1) 2X4 KING STUD AT EACH END, U.N.O.
46. AT ANY SOLE PLATES OR TOP PLATES CUT FOR PIPES, PROVIDE A .058" THICK (16 GA.) AND 1/2" WIDE PLATE ACROSS EACH SIDE OF OPENING WITH NOT LESS THAN (6) 16d NAILS.
47. PROVIDE SOLID BLOCKING AT SOFFIT CEILINGS.
48. SHEAR SHALL BE CONTINUOUS FROM BOTTOM PLATES TO TOP PLATES, U.N.O.
49. STAIR STRINGER SHALL BE 2X12 DF#1 U.N.O.
50. A SINGLE TOP PLATE IS PERMITTED PROVIDED THE PLATE IS ADEQUATELY TIED AT JOINTS, CORNERS AND INTERSECTING WALLS BY AT LEAST THE EQUIVALENT OF 3 IN. x 6 IN. x .036 IN. THICK GALVANIZED STEEL PLATE THAT IS NAILED TO EACH WALL OR SEGMENT OF WALL BY (6) 8d NAILS OR EQUIVALENT.

# LATERAL SHEAR NOTES:

- ( 2013 CBC, SDPWS-2008 ; SEISMIC DESIGN CATEGORY D & E ) FRAMING MEMBERS DOUGLAS FIR-LARCH
- VERTICAL:
10. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 6" O.C AT EDGES AND 12" O.C AT FIELD ..... 260 PLF
  11. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 4" O.C AT EDGES AND 12" O.C AT FIELD ..... 350 PLF
  12. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 3" O.C AT EDGES AND 12" O.C AT FIELD ..... 490 PLF
  13. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 640 PLF
  14. 1/2"(OR 15/32) WOOD STRUCTURAL PANEL WITH 10d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 770 PLF
  15. 1/2"(OR 15/32) STRUCT. I WOOD PANEL WITH 10d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 870 PLF
- HORIZONTAL: (3/8" @ CEILING LIDS, 15/32" @ ROOF SHTG) (3/8" PANEL VALUES AND NAILING BELOW MAY BE USED FOR 15/32" PANELS)
20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 6" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 240 PLF
  21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 320 PLF
  22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2.5" O.C STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O

**FOUNDATION NOTES:**

- ALL DIMENSIONS SHALL BE VERIFIED WITH THE ARCHITECTS DRAWINGS ANY DISCREPANCIES SHALL BE RESOLVED PRIOR TO COMMENCING OF WORK.
- D.F.P.T. PLATE TO BE SECURED WITH 1/2" DIAMETER BY 10" LONG ANCHOR BOLTS WITH A STANDARD CUT WASHER EMBEDDED AT LEAST 7" INTO CONCRETE WITH A MAXIMUM SPACING OF 72" O.C. THERE SHALL BE A MINIMUM OF TWO BOLTS PER PIECE OF FOUNDATION PLATE WITH ONE BOLT LOCATED WITHIN 12" MAX. & 4-1/2" MIN. OF EA. END OF EA. PIECE. **AT SHEAR WALLS** A PROPERLY SIZED NUT AND 3"x3"x.229" THICK WASHER SHALL BE TIGHTENED ON EA. BOLT TO THE PLATE. HOLE IN PLATE WASHER CAN BE DIAGONALLY SLOTTED W/ A WIDTH OF UP TO 3/16" LARGER THAN BOLT DIAMETER & A SLOT LENGTH NOT TO EXCEED 1 3/4". PROVIDED A STANDARD CUT WASHER IS PLACED BETWEEN THE PLATE WASHER & THE NUT. U.N.O. BY SUB LETTER 'C' WHEN A CUT WASHER IS OKAY.
  - ALL INTERIOR NON-SHEAR WALLS ARE TO BE SECURED WITH SHOT PINS INSTALLED PER MANUFACTURERS RECOMMENDATIONS, U.N.O. STRUCTURAL ENGINEERS CALCULATIONS GOVERN IN ALL CASES.
  - INSTALL ALL SIMPSON (OR APPROVED EQUAL) FOUNDATION HARDWARE PER MANUFACTURERS RECOMMENDATIONS. DEEPEN FOOTING WHERE NECESSARY TO PROVIDE ANCHOR EMBEDMENT AT HOLDOWN LOCATIONS.

**NOTE:**

WHEN REQUIRED BY LOCAL BUILDING DEPARTMENT ALL ANCHOR BOLTS AND HOLDOWN BOLTS TO BE SET IN PLACE PRIOR TO CITY FOUNDATION INSPECTION

**FOUNDATION INFORMATION:**

- FOUNDATION SIZES, DEPTHS, AND REINFORCEMENT ARE AS RECOMMENDED WITHIN THE OWNER/DEVELOPER'S SOILS ENGINEERS REPORT. SOILS ENGINEER TO PROVIDE FOUNDATION INSPECTION AS OUTLINED IN LATEST SOIL REPORT.
- OWNER/DEVELOPER AND SUBCONTRACTORS ARE TO REVIEW THE SOILS REPORT PRIOR TO COMMENCING CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE OWNER, DEVELOPER AND SUBCONTRACTOR TO VERIFY THAT THE REPORT IS CURRENT AND PLAN REQUIREMENTS ARE CONSISTENT WITH ANY UPDATED SOIL REPORTS. ESI/FME IS TO BE SUPPLIED WITH ALL UPDATED REPORTS.

**ANCHOR BOLT LEGEND:**

- \* AB32 : 1/2" DIA. X 10" ANCHOR BOLTS AT 32" O.C.
- AB24 : 1/2" DIA. X 10" ANCHOR BOLTS AT 24" O.C.
- AB# : 1/2" DIA. X 10" ANCHOR BOLTS AT #" O.C.
- 2AB : (2) 1/2" DIA X 10" ANCHOR BOLTS.
- 3AB : (3) 1/2" DIA X 10" ANCHOR BOLTS.
- #AB : (#) 1/2" DIA X 10" ANCHOR BOLTS.
- #ABc : c DENOTES STANDARD CUT WASHERS OKAY IN LIEU OF 3" SD. ONLY REQUIRED.
- 2-#4 : PROVIDE A TOTAL OF 2 #4 AT TOP AND 2 #4 AT BOTTOM OF FOOTING, 4" PAST POSTS.
- 3-#4 : PROVIDE A TOTAL OF 3 #4 AT TOP AND 3 #4 AT BOTTOM OF FOOTING, 4" PAST POSTS.
- 2-#5 : PROVIDE A TOTAL OF 2-#5 AT TOP AND 2-#5 AT BOTTOM OF FOOTING, 6" PAST POSTS.
- HDU2 : (1) SIMPSON HDU2 PER POST.
- HDU# : (1) SIMPSON HDU# PER POST.
- HTT4 : (1) SIMPSON HTT4 PER POST.
- HTT5 : (1) SIMPSON HTT5 PER POST.
- PHD6 : (1) SIMPSON PHD6 PER POST.
- HD8A : (1) SIMPSON HD8A PER POST.
- HD10A : (1) SIMPSON HD10A PER POST.
- HD14A : (1) SIMPSON HD14A PER POST.
- HD08 : (1) SIMPSON HD08-SDS3 PER POST.
- HHQ11 : (1) SIMPSON HHQ11-SDS2.5 PER POST.
- HHQ14 : (1) SIMPSON HHQ14-SDS2.5 PER POST.

REFER TO ARCHITECTURAL PLANS FOR ALL DIMENSIONS

\* ALT. TO 1/2" ANCHOR BOLTS SIMPSON MASA AT A 1-1 RATIO

ALL GRADE BEAMS 8"x22 1/2" THICK W/ 2-#5 TOP & BOTTOM, U.N.O. W/ #3 TIES @ 12" O.C., U.N.O.

ALL PIERS TYPE [A] UNLESS NOTED OTHERWISE (U.N.O.)

PIER SCHEDULE			SEE (31) FOR TYP. CONN.
TYPE	DEPTH INTO BEDROCK	CAPACITY	VERT. REINF.
A	1'-0"	11,175 *	(5) #6
B	10'-0"	18,840 *	(10) #6
C	20'-0"	43,000 *	-

5" MIN. INTO BEDROCK

f=500 pcf


UPPER STRATA

BEDROCK

- ALL PIERS TO BE INTERCONNECTED WITH GRADE BEAMS

PIERS: #6 @ 12" PIER W/ #3 TIES AT 12" o/c PIERS SHALL PENETRATE AT LEAST 5'-0" INTO BEDROCK & A MIN. OF 10' BELOW THE LOWEST ADJACENT GRADE AS IDENTIFIED BY THE SOILS ENGINEER DURING CONSTRUCTION (SEE SOILS REPORT FOR MORE RECOMMENDATIONS.)

THE EXCAVATION OF ALL DRILLED SHAFTS SHOULD BE OBSERVED BY A CORNERSTONE REPRESENTATIVE TO CONFIRM THE SOIL PROFILE, VERIFY THAT THE PIERS EXTEND THE MINIMUM DEPTH INTO SUITABLE MATERIALS AND THAT THE PIERS ARE CONSTRUCTED IN ACCORDANCE WITH OUR RECOMMENDATIONS AND PROJECT REQUIREMENTS. THE DRILLED SHAFTS SHOULD BE STRAIGHT, DRY AND RELATIVELY FREE OF LOOSE MATERIAL BEFORE REINFORCING STEEL IS INSTALLED AND CONCRETE IS PLACED. IF GROUND WATER CANNOT BE REMOVED FROM THE EXCAVATIONS PRIOR TO CONCRETE PLACEMENT, DRILLING SLURRY OR CASING MAY BE REQUIRED TO STABILIZE THE SHAFT AND THE CONCRETE SHOULD BE FLACED USING A TREMIE PIPE, KEEPING THE TREMIE PIPE BELOW THE SURFACE OF THE CONCRETE TO AVOID ENTRAPMENT OF WATER OR DRILLING SLURRY IN THE CONCRETE.



**FOUNDATION PLAN 7A**  
SCALE : 1/4" = 1'-0"


**FOUNDATION PLAN**

HIGHLAND ESTATES  
LOT 7: 2139 TICONDEROGA DR.  
SAN MATEO, CA  
THE CHAMERLAIN GROUP



DRAWN -  
CHECKED -  
PLOT DATE 05/23/2017  
JOB NO. E776  
SHEET

**S7-1**



### LATERAL SHEAR NOTES:

- ( 2013 CBC, SDPWS-2008 ; SEISMIC DESIGN CATEGORY D & E ) FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16" O.C.
- TABLE 4.3A, AFPA SDPWS-2008 }
- 10. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 6" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 260 PLF
  - 11. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 4" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 350 PLF
  - 12. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 3" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 490 PLF
  - 13. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 640 PLF
  - 14. 1/2"(OR 15/32) WOOD STRUCTURAL PANEL WITH 10d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 770 PLF
  - 15. 1/2"(OR 15/32) STRUCT. 1 WOOD PANEL WITH 10d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 870 PLF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 24" O.C.
- 20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 6" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 240 PLF
  - 21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2.5" O.C. STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 480 PLF
  - 23. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 545 PLF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16" O.C.
- 24. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 6" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 25. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 425 PLF
  - 26. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2.5" O.C. STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 640 PLF
  - 27. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 730 PLF

- NOTES:
- A. WOOD STRUCTURAL PANEL: MATERIAL APPROVED BY APA, PFS/TECO OR PITTSBURGH TESTING LABORATORIES THESE VALUES ARE FOR DOUG-FIR LARCH OR SOUTHERN PINE. OTHER LUMBER SPECIES MAY DIFFER IN SHEAR CAPACITIES.
  - B. PROVIDE 2X BLOCKING AT HORIZONTAL WOOD STRUCTURAL PANEL JOINTS. FRAMING AT ADJOINING PANEL EDGES SHALL BE 3X WHEN NAILING IS 2.5" O.C. OR LESS.
  - C. WHERE WOOD STRUCTURAL PANEL IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C., PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS OR FRAMING SHALL BE 3X OR WIDER AND NAILS STAGGERED ON EACH SIDE. FOR SHEAR WALLS USE THE FOLLOWING:
    - 1) USE 3x MEMBER @ PANEL JOINTS & HORIZONTAL BLOCKING
    - 2) EDGE NAILING SHALL BE STAGGERED
  - D. 10d SHORT BOX NAILS MAY BE USED IN LIEU OF 8d COMMON NAILS @ SHEAR WALLS ONLY.
  - E. REQUIRED PLATE WASHERS AT SHEAR WALLS TO BE: 3" x 3" x .229" STEEL PLATE U.N.O. WITH SUB SCRIPT c WHERE STANDARD CUT WASHERS ARE OKAY (SDPWS SECT. 4.3.6.4.3) WASHER MAY BE SLOT CUT PROVIDED A STANDARD CUT WASHER IS PROVIDED BETWEEN THE WASHER AND NUT. WASHER TO BE INSTALLED WITHIN 1/2" OF SHEATHED SIDE OF PLATE.
  - G. A STANDARD CUT WASHER MAY BE USED AT ALL NON-SHEAR WALL LOCATIONS WITH ANCHOR BOLTS.


HORIZONTAL: ALL ROOF AND FLOOR SHEATHING TO BE EXPOSURE 1 OR EXTERIOR (TABLE 2306.2.1)

ROOF: JUST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL PII 32/16, WITH 8d AT EDGES AND BOUNDARIES, 12" O.C. FIELD

FLOOR: JUST SPACING EQUAL TO OR LESS THAN 16" O.C. 19/32" WOOD STRUCTURAL PANEL T&G SHTG, PII 32/16, w/10d's AT EDGES AND BOUNDARIES, 12" O.C. FIELD. JUST SPACING EQUAL TO OR LESS THAN 20" O.C. 19/32" WOOD STRUCTURAL PANEL T&G SHTG, PII 40/20, w/10d's AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD. JUST SPACING EQUAL TO OR LESS THAN 24" O.C. 23/32" WOOD STRUCTURAL PANEL T&G SHTG, PII 46/24, w/10d's AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.

\* PANEL EDGES SHALL JOINTS OR SHALL BE SUPPORTED WITH BLOCKING NOT REQUIRED WHEN LIGHTWEIGHT CONCRETE IS PLACED OVER SUBFLOOR.

### FRAMING LEGEND:



MARK	SPACING	SIZE & MANUFACTURER OPTIONS
D-	I-JOIST @ 12" O.C.	1 1/8" TJI / 230
R-	I-JOIST @ 16" O.C.	1 1/2" TJI / 230
S-	I-JOIST @ 19.2" O.C.	1 1/2" TJI / 230
U-	I-JOIST @ 12" O.C.	1 1/4" TJI / 230
V-	I-JOIST @ 16" O.C.	1 1/2" TJI / 230
W-	I-JOIST @ 19.2" O.C.	1 1/2" TJI / 230
X-	I-JOIST @ 12" O.C.	1 1/4" TJI / 360
Y-	I-JOIST @ 16" O.C.	1 1/2" TJI / 360
Z-	I-JOIST @ 19.2" O.C.	1 1/2" TJI / 360

MARK:	DESCRIPTION	CEILING JOIST SCHEDULE
SPN12:	16d SOLE PLATE NAILING @ 12" O.C.	SIZE   SPACING   SPAN GRADE NO. 2
SPN18:	16d SOLE PLATE NAILING @ 18" O.C.	2x4   12" O.C.   9'-1"
SPN24:	16d SOLE PLATE NAILING @ 24" O.C.	16" O.C.   8'-4"
SPN8:	16d SOLE PLATE NAILING @ 8" O.C.	24" O.C.   7'-2"
SPN6:	16d SOLE PLATE NAILING @ 6" O.C.	2x6   12" O.C.   14'-6"
SPN4:	16d SOLE PLATE NAILING @ 4" O.C.	16" O.C.   13'-4"
SPN3:	16d SOLE PLATE NAILING @ 3" O.C.	24" O.C.   11'-6"
SPN2:	16d SOLE PLATE NAILING @ 2" O.C.	2x8   12" O.C.   20'-4"
SPN1:	16d SOLE PLATE NAILING @ 1" O.C.	16" O.C.   18'-3"
SCR1:	1/4" x 4 1/2" SDS SCREWS @ 3" O.C.	24" O.C.   16'-1"

- M=L INDICATES (1) 1 3/4" x DEPTH OF JOIST MICROLAM LVL 1.9 E
- PSL INDICATES PARALLAM PSL 2.0 E
- TSR INDICATES 1 1/2" BY DEPTH OF JOIST TIMBERSTRAND RIM
- E.N. INDICATES EDGE NAILING @ 6" O.C.
- G.T. GIRDER TRUSS
- C-TM INDICATES CONNECTION BY TRUSS MANUFACTURER
- HEADERS AND BEAMS, REFER TO ENGINEERING CALCS.
- INDICATES INTERIOR BEARING WALL
- NOTE: APPLY SHEAR PRIOR TO FRAMING OF PERPENDICULAR WALL AND/OR BOX-OUTS. (WHERE APPLICABLE)

## FLOOR FRAMING PLAN 7A


SCALE : 1/4" = 1'-0"

REVISIONS
6-2-17 BDC


ESIFME INC.  
STRUCTURAL ENGINEERS  
1800 E. 16TH ST. SUITE B  
SANTA ANA, CA 92701  
PHONE: 714-895-2800  
FAX: 714-895-2819  
REG. NO. 05-023207

## FLOOR FRAMING PLAN

HIGHLAND ESTATES  
LOT 7: 2139 TICONDEROGA DR.  
SAN MATEO, CA  
THE CHAMERLAIN GROUP



DRAWN
CHECKED
PLOT DATE 05/23/2017
JOB NO. E776
SHEET
<b>S7-2</b>
SHEET: 3 OF: 6



### LATERAL SHEAR NOTES:


- ( 2013 CBC, SDPWS-2008 ; SEISMIC DESIGN CATEGORY D & E ) FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16' O.C
- 10. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 6" O.C AT EDGES AND 12" O.C AT FIELD ..... 260 PLF
  - 11. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 4" O.C AT EDGES AND 12" O.C AT FIELD ..... 350 PLF
  - 12. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 3" O.C AT EDGES AND 12" O.C AT FIELD ..... 490 PLF
  - 13. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 640 PLF
  - 14. 1/2"(OR 15/32) WOOD STRUCTURAL PANEL WITH 10d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 770 PLF
  - 15. 1/2"(OR 15/32) STRUCT. 1 WOOD PANEL WITH 10d COMMON NAILS AT 2" O.C AT EDGES AND 12" O.C AT FIELD ..... 870 PLF

- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 24" O.C
- 20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 6" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 240 PLF
  - 21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 320 PLF
  - 22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2.5" O.C STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O.C AT FIELD ..... 480 PLF
  - 23. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2" O.C STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C AT FIELD ..... 545 PLF
  - 24. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 6" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 320 PLF
  - 25. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 4" O.C AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C AT FIELD ..... 425 PLF
  - 26. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2.5" O.C STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O.C AT FIELD ..... 640 PLF
  - 27. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2" O.C STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C AT FIELD ..... 730 PLF

NOTES:  
 A. WOOD STRUCTURAL PANEL: MATERIAL APPROVED BY APA, PFS/TECO OR PITTSBURGH TESTING LABORATORIES THESE VALUES ARE FOR DOUG-FIR LARCH OR SOUTHERN PINE. OTHER LUMBER SPECIES MAY DIFFER IN SHEAR CAPACITIES.  
 B. PROVIDE 2X BLOCKING AT HORIZONTAL WOOD STRUCTURAL PANEL JOINTS. FRAMING AT ADJOINING PANEL EDGES SHALL BE 3X WHEN NAILING IS 2.5" O.C. OR LESS.  
 C. WHERE WOOD STRUCTURAL PANEL IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C, PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS OR FRAMING SHALL BE 3X OR WIDER AND NAILS STAGGERED ON EACH SIDE. FOR SHEAR WALLS TO USE THE FOLLOWING:  
 1) USE 3x MEMBER @ PANEL JOINTS & HORIZONTAL BLOCKING  
 2) EDGE NAILING SHALL BE STAGGERED  
 3) 10d SHORT BOX NAILS MAY BE USED IN LIEU OF 8d COMMON NAILS @ SHEAR WALLS ONLY.  
 F. REQUIRED PLATE WASHERS AT SHEAR WALLS TO BE: 3" x 3" x .229" STEEL PLATE U.N.O. WITH SUB SCRIPT c WHERE STANDARD CUT WASHERS ARE OKAY (SDPWS SECT. 4.3.6.4.3) WASHER MAY BE SLOT CUT PROVIDED A STANDARD CUT WASHER IS PROVIDED BETWEEN THE WASHER AND NUT. WASHER TO BE INSTALLED WITHIN 1/2" OF SHEATHED SIDE OF PLATE.  
 G. A STANDARD CUT WASHER MAY BE USED AT ALL NON-SHEAR WALL LOCATIONS WITH ANCHOR BOLTS.

HORIZONTAL: ALL ROOF AND FLOOR SHEATHING TO BE EXPOSURE 1 OR EXTERIOR (TABLE 2306.2.1)  
 ROOF: JUST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL PII 32/16, WITH 8d'S AT 6" O.C AT EDGES AND BOUNDARIES, 12" O.C FIELD.  
 HORIZONTAL DIAPHRAGM VALUES FOR 3/8" WOOD STRUCTURAL PANELS MAY BE USED FOR 15/32" WOOD STRUCTURAL PANELS. U.N.O.  
 FLOOR: \* JUST SPACING EQUAL TO OR LESS THAN 16" O.C. 19/32" WOOD STRUCTURAL PANEL T&G SHG, PII 32/16, w/10d'S AT 6" O.C AT EDGES AND BOUNDARIES, 12" O.C FIELD.  
 \* JUST SPACING EQUAL TO OR LESS THAN 20" O.C. 19/32" WOOD STRUCTURAL PANEL T&G SHG, PII 40/20, w/10d'S AT 6" O.C AT EDGES AND BOUNDARIES, 12" O.C FIELD.  
 \* JUST SPACING EQUAL TO OR LESS THAN 24" O.C. 23/32" WOOD STRUCTURAL PANEL T&G SHG, PII 46/24, w/10d'S AT 6" O.C AT EDGES AND BOUNDARIES, 12" O.C FIELD.  
 \* PANEL EDGES SHALL HAVE APPROVED TAG JOINTS OR SHALL BE SUPPORTED WITH BLOCKING NOT REQUIRED WHEN LIGHTWEIGHT CONCRETE IS PLACED OVER SUBFLOOR.

### FRAMING LEGEND:



MARK	SPACING	SIZE & MANUFACTURER OPTIONS
A	2x6 AT 12" O.C	11 7/8" TJI / 230
B	2x6 AT 16" O.C	-
C	2x8 AT 24" O.C	-
D	2x8 AT 12" O.C	-
E	2x8 AT 16" O.C	-
F	2x8 AT 24" O.C	-
G	2x10 AT 12" O.C	-
H	2x10 AT 16" O.C	-
I	2x10 AT 24" O.C	-
J	2x10 AT 12" O.C	14" TJI / 230
K	(2)2x10 AT 16" O.C	-
L	2x12 AT 12" O.C	-
M	2x12 AT 16" O.C	-
N	2x12 AT 24" O.C	14" TJI / 360
P	(2)2x12 AT 16" O.C	-
T	TRUSS AT 24" O.C	-

M=L INDICATES (1) 1 3/4" x DEPTH OF JOIST MICROLAM LVL 1.9 E  
 PSL INDICATES PARALAM PSL 2.0 E  
 TSR INDICATES 1 1/2" BY DEPTH OF JOIST TIMBERSTRAND RIM  
 E.N. INDICATES EDGE NAILING @ 6" O.C.  
 G.T. GIRDER TRUSS  
 C-TM INDICATES CONNECTION BY TRUSS MANUFACTURER  
 # HEADERS AND BEAMS, REFER TO ENGINEERING CALCS.  
 ■ INDICATES INTERIOR BEARING WALL  
 NOTE: APPLY SHEAR PRIOR TO FRAMING OF PERPENDICULAR WALL AND/OR BOX-OUTS. (WHERE APPLICABLE)

MARK	DESCRIPTION	SIZE	SPACING	SPAN GRADE NO 2
SPN12	16d SOLE PLATE NAILING @ 12" O.C.	2x4	12" O.C.	9'-1"
SPN18	16d SOLE PLATE NAILING @ 18" O.C.	2x4	18" O.C.	8'-4"
SPN24	16d SOLE PLATE NAILING @ 24" O.C.	2x4	24" O.C.	7'-2"
SPN6	16d SOLE PLATE NAILING @ 6" O.C.	2x6	12" O.C.	14'-6"
SPN4	16d SOLE PLATE NAILING @ 4" O.C.	2x6	16" O.C.	13'-4"
SPN3	16d SOLE PLATE NAILING @ 3" O.C.	2x6	24" O.C.	11'-6"
SPN2	16d SOLE PLATE NAILING @ 2" O.C.	2x8	12" O.C.	20'-4"
SPN1	16d SOLE PLATE NAILING @ 1" O.C.	2x8	16" O.C.	18'-3"
SCR1	1/4" x 4 1/2" SDS SCREWS @ 3" O.C.	2x4	24" O.C.	16'-1"

- AT GABLE END WALLS IF PLY SHEAR IS RUN UP TO AND NAILED TO BOT. CHORD OF TRUSS -OK TO OMIT A35'S AND PLATE SPICE NAILING
- AT EXT WALLS IF PLY SHEAR IS RUN UP TO AND NAILED TO T.S.R. -OK TO OMIT A35'S AND PLATE SPICE NAILING AND 2ND FLOOR SPECIAL SILL PLATE NAILING, BUT ADD ST6224 AT EACH RIM SPLICE.

REVISIONS
6-2-17 BDC

ESIFME INC.  
 STRUCTURAL ENGINEERS  
 1800 E. 16TH ST. SUITE B  
 SANTA ANA, CA 92701  
 PHONE: 714-895-2800  
 FAX: 714-895-2819  
 REG. # E776 05/23/2017

## ROOF FRAMING PLAN

HIGHLAND ESTATES  
 LOT 7: 2139 TICONDEROGA DR.  
 SAN MATEO, CA  
 THE CHAMERLAIN GROUP




DRAWN
CHECKED
PLOT DATE 05/23/2017
JOB NO. E776
SHEET
<b>S7-3</b>
SHEET: 4 OF: 6


## ROOF FRAMING PLAN 7A

SCALE : 1/4" = 1'-0"


N:\Projects\7761007\7761007.dwg, 03/23/2017 11:48:12 AM, Baur/BDC




**17 SHEAR TRANSFER**




**13 ROOF CONNECTION**




**9 PERPENDICULAR DRAG STRUT**




**5 NON-BEARING WALL CONNECTION**




**1 EAVE TRUSS SHEAR CONNECTION**




**18 DRAG TIE TO TRUSS**




**14 POST TO POST HOLDOWN**




**10 WALL @ CONG OR CMU WALL**




**6 DRAG CONNECTION**




**2 DRAG TRUSS SHEAR TRANSFER**




**19 DECK JOIST CONNECTION**




**15 PAD DETAIL**




**11 JOIST DRAG STRUT**




**7 SPECIAL SHEAR AT WINDOW OPENING**




**3 DRAG DETAIL**




**20 ROOF TO WALL SHEAR TRANSFER**




**16 SHEAR TRANSFER**



**12 INTERRUPTED DRAGS**



**8 JOIST SHEAR CONNECTION**



**4 EXTERIOR GRADE BEAM FOR HFX**


REVISIONS

NO.	DATE	DESCRIPTION
6-2-17	EDC	


ESIFME INC.  
STRUCTURAL ENGINEERS  
1800 E. 16TH ST. STE. B  
SANTA ANA, CA 92701  
PHONE: 714-855-2800  
FAX: 714-855-2819  
JULY 2017

**STRUCTURAL  
DETAILS**


HIGHLAND ESTATES  
LOT 7: 2139 TICONDEROGA DR.  
SAN MATEO, CA  
THE CHAMERLAIN GROUP




DRAWN -  
CHECKED -  
PLOT DATE  
05/23/2017  
JOB NO.  
E776  
SHEET  
**SD1**




**33 EXTERIOR FOOTING**




**34 EXTERIOR GARAGE FOOTING**




**35 HOLDOWN DETAIL SSTB BOLT**




**36 EXTERIOR WALL**




**29 SLAB EDGE AT GARAGE**




**30 SHEAR TRANSFER @ CALIF FRAMING**




**31 CAISSON SECTION**




**32 FOUNDATION ACCESS**




**25 GRADE BEAM**




**26 HOLDOWN**




**27 HOUSE TO GARAGE**




**28 DECK DETAIL**




**21 CAISSON / G.B. CONN.**



**22 G.B. INTERSECTION**



**23 GRADE BM @ CORNER**



**24 INTERIOR GRADE BM**

REVISIONS

6-2-17	BC
--------	----

ESI/FME INC.  
 STRUCTURAL ENGINEERS  
 1800 E. 16TH ST. STE. B  
 SANTA ANA, CA 92701  
 PHONE: 714-895-2800  
 FAX: 714-895-2819  
 JN-E776 05/23/2017

F M E S I


**STRUCTURAL DETAILS**

HIGHLAND ESTATES  
 LOT 7: 2139 TICONDEROGA DR.  
 SAN MATEO, CA  
 THE CHAMERLAIN GROUP

REGISTERED PROFESSIONAL ENGINEER  
 CIVIL STATE OF CALIFORNIA  
 C 30407

DRAWN	-
CHECKED	-
PLOT DATE	05/23/2017
JOB NO.	E776
SHEET	
<b>SD2</b>	


**SECTION A**



1. CAVITY ORIENTED FOR CONNECTION ACCESS.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT AT BOTH ENDS. SEE HFX1 FOR ANCHORAGE.
3. 8 INCH FRAMING ABOVE (MIN).
4. A 2x FILLER WITH 1/4" x 4-1/2" MIN USP-WS SCREWS (OR EQUAL) IS PERMITTED.
5. WOOD BACKING FIELD INSTALLED AS NEEDED.

**BACK TO BACK INSTALLATION**


11



1. 4x WOOD FILLER WITH USP MP4-F CONNECTORS (OR EQUAL) BY BUILDING DESIGN PROFESSIONAL.
2. 1/4" x 3" (MIN) USP "WS-SERIES" SCREWS (OR EQUAL). QUANTITY PER TABLES
3. ADJACENT FRAMING WITH 1/4" DIAMETER SCREWS IS INSTALLED AT THE EDGES WHEN INSTALLING A 4x FILLER ABOVE OR WHEN SPECIFIED BY DESIGN PROFESSIONAL.
4. OPTIONAL LEDGER PRE-DRILL 3/16" DIA. HOLES, EVENLY SPACED IN FACE OF PANEL AND INSTALL 1/4" DIA. WOOD SCREWS INTO 2x (MIN.) WOOD LEDGER LOCATED IN PANEL CAVITY.
5. CONNECTOR AND ATTACHMENT BY BUILDING DESIGN PROFESSIONAL.

**TOP CONNECTION W/ 4x FILLER**


10



1. 15# FELT OR EQUIVALENT MOISTURE BARRIER RECOMMENDED BETWEEN PANEL BASE AND CONCRETE.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT AT BOTH ENDS. SEE HFX1 FOR ANCHORAGE.
3. ADJACENT FRAMING WITH 1/4" DIAMETER SCREWS IS INSTALLED AT THE EDGES WHEN INSTALLING A 4x FILLER ABOVE OR WHEN SPECIFIED BY DESIGN PROFESSIONAL.

**RAISED FLOOR HEAD-OUT**

9




1. 15# FELT OR EQUIVALENT MOISTURE BARRIER RECOMMENDED BETWEEN PANEL BASE AND CONCRETE.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT. SEE HFX1 FOR ANCHORAGE.

**INSTALLATION ON 2x PLATE**

8

**NOTES:**


- A) OUT OF PLANE FORCES TO BE RESISTED BY OTHER FRAMING MEMBERS PER THE BUILDING DESIGN PROFESSIONAL.
- B) BALLOON WALL APPLICATIONS REQUIRE HIGH STRENGTH ANCHORAGE. SEE FOUNDATION PLAN AND ANCHORAGE TABLES ON SHEET HFX-1



1. 15# FELT OR EQUIVALENT MOISTURE BARRIER RECOMMENDED BETWEEN PANEL BASE AND CONCRETE.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT. SEE HFX1 FOR ANCHORAGE.
3. WELDED CONNECTION BY HARDY FRAMES, INC. (NO FIELD CONNECTION REQUIRED).
4. A 2x FILLER WITH 1/4" x 4-1/2" MIN USP-WS SCREWS (OR EQUAL) IS PERMITTED.
5. WHEN REQUIRED BY THE BUILDING DESIGN PROFESSIONAL ATTACH ADJACENT WOOD MEMBERS TO PANEL WITH 1/4" USP-WS SCREWS (OR EQUAL) THROUGH THE PANEL EDGE INTO THE WOOD MEMBER.

**BALLOON WALL INSTALLATION**


7



1. 1/4" x 3" (MIN) USP "WS-SERIES" SCREWS (OR EQUAL). QUANTITY PER TABLES
2. 1/4" x 4-1/2" (MIN) USP "WS-SERIES" SCREWS (OR EQUAL). QUANTITY PER TABLES
3. 2x WOOD FILLER.

**TOP PLATE CONNECTIONS**


6



1. 15# FELT OR EQUIVALENT MOISTURE BARRIER RECOMMENDED BETWEEN PANEL BASE AND CONCRETE.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT AT BOTH ENDS. SEE HFX1 FOR ANCHORAGE.

**INSTALLATION ON FOUNDATION**

5




1. PLUS OR MINUS 1-1/2" GAP TO BE FILLED WITH MIN 5,000 PSI STRENGTH NON-SHRINK GROUT.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT. SEE HFX1 FOR ANCHORAGE.

**INSTALLATION ON NUTS&WASHERS**

4

**NOTES:**


- ATTACHMENTS MAY BE MADE AT SCREW HOLES PROVIDED OR WITH SELF TAPPING SCREWS (#12 AT EDGES, #10 AT FACE).



1. TRIMMERS PROVIDE FULL BEARING FOR HEADER ABOVE, DESIGN AND CONNECTIONS BY OTHERS.
2. 6x HEADER.
3. WOOD MEMBERS MAY BE INSERTED VERTICALLY OR HORIZONTALLY IN CAVITY FOR BACKING AS NEEDED.

**6x HEADER ABOVE-SECTION**


3



- 1A. WELDED STRAPS ARE AVAILABLE FROM MANUFACTURER WHEN REQUIRED BY THE DESIGN PROFESSIONAL.
- 1B. WHEN STRAPS ARE FIELD INSTALLED THE DESIGN AND CONNECTION IS BY THE DESIGN PROFESSIONAL. CONNECTION TO PANEL WITH SELF TAPPING SCREWS IS PERMITTED.
2. A 2x WOOD FILLER WITH 1/4"x4-1/2" (MIN.) USP "WS" SERIES SCREWS OR EQUAL IS PERMITTED.
3. WHEN CRIPPLE STUDS OCCUR, SHEAR TRANSFER DESIGN TO BE PER THE DESIGN PROFESSIONAL.
- 4A. THERE IS NO "INSIDE" OR "OUTSIDE" FACE OF PANEL. TO PREVENT THE NEED FOR ADDITIONAL HOLES ORIENT THE PANEL CAVITY TOWARD THE FIXTURE BEING INSTALLED.
- 4B. A 1" DIA. HOLE MAY BE ADDED IN THE PANEL FACE WHEN IT IS LOCATED IN THE UPPER HALF OF THE PANEL HEIGHT AND IS 4" MIN. FROM ANY EDGE. FOR PANELS MORE THAN 12" WIDE, ADDITIONAL HOLES MUST ALSO BE 1" MINIMUM ABOVE AND BELOW THE 3" DIA. HOLE PROVIDED.
- 4C. FOR HOLES LARGER THAN 1" DIA. OR TO ADD MORE THAN ONE HOLE CONTACT HARDY FRAMES, INC.

**TOP CONNECTION TO HEADER**

2



1. 15# FELT OR EQUIVALENT MOISTURE BARRIER RECOMMENDED BETWEEN PANEL BASE AND CONCRETE.
2. 1 EA. HARDENED ROUND, 2 EA. SAE OR 2 EA. ROUND-FLAT WASHERS AND 1 EA. GRADE 8 HEX NUT. SEE HFX1 FOR ANCHORAGE.
3. ADJACENT FRAMING OPTIONAL U.N.O. BY BUILDING DESIGN PROFESSIONAL.

**INSTALLATION ON CURB**

1

**HFX-SERIES 78 IN. THRU 13 FOOT**

Model Number	Net Height (in)	Depth (in)	Hold Down Diameter <sup>1</sup> (in)	Top Screw Qty <sup>2</sup> (ea)	Screw Qty Available at Edges (ea) <sup>3</sup>	
HFX-12,15,18,21 & 24x78	78	3-1/2	1-1/8	9" Width = 5	4	
HFX-9x79.5	79-1/2			12" Width = 6		
HFX-12,15,18,21 & 24x8	92-1/4			15" Width = 8		
HFX-9x8	93-3/4			18" Width = 10		
HFX-12,15,18,21 & 24x9	104-1/4			21" Width = 12		
HFX-12,15,18,21 & 24x10	116-1/4			24" Width = 14		
HFX-15,18,21 & 24x11	128-1/4	3-1/2	1-1/8	15" Width = 8	6	
HFX-15,18,21 & 24x12	140-1/4			18" Width = 10		
HFX-15,18,21 & 24x13	152-1/4			21" Width = 12		
HFX-15,18,21 & 24x14	164-1/4	3-1/2	1-1/8	15" Width = 8	7	
HFX-15,18,21 & 24x15	176-1/4			18" Width = 10		
HFX-15,18,21 & 24x16	188-1/4			21" Width = 12		
HFX-15,18,21 & 24x17	200-1/4			24" Width = 14		
HFX-15,18,21 & 24x18	212-1/4			8		
HFX-15,18,21 & 24x19	224-1/4					
HFX-15,18,21 & 24x20	236-1/4					




**BALLOON PANELS 14 FEET THRU 20 FEET**

Model Number	Net Height (in)	Depth (in)	Hold Down Diameter <sup>1</sup> (in)	Top Screw Qty <sup>2</sup> (ea)	Screw Qty Available at Edges (ea) <sup>3</sup>	
HFX-15,18,21 & 24x14	164-1/4	3-1/2	1-1/8	15" Width = 8	6	
HFX-15,18,21 & 24x15	176-1/4			18" Width = 10		
HFX-15,18,21 & 24x16	188-1/4			21" Width = 12		
HFX-15,18,21 & 24x17	200-1/4			24" Width = 14		
HFX-15,18,21 & 24x18	212-1/4			8		
HFX-15,18,21 & 24x19	224-1/4					
HFX-15,18,21 & 24x20	236-1/4					

- 1) Hold down bolts connect to the Panel base with (1 ea) Hardened Round, (2 ea) Round-Flat or (2 ea) SAE Washers below (1 ea) Grade 8 Hex Nut on each rod or as specified by the Building Design Professional.
- 2) 1/4" diameter USP-WS Series screws (or equal). Length is 3" (minimum) when attached directly to the collector and 4-1/2" (minimum) when installing a 2x filler above the Panel.
- 3) Adjacent framing with 1/4" diameter screws is required at the edges when installing a 4X filler above or when specified by the Design Professional.

**INSTALLATION INSTRUCTIONS**

- A) When installing directly on concrete, place Panel over bolts and connect with (1 ea) Hardened Round, (2 ea) Round-Flat or (2 ea) SAE Washers below (1 ea) Grade 8 or 2H Heavy Hex Nut. Secure with a deep socket (recommended) until "Snug Tight".
- B) If bottom connection is not detailed on plans, confirm with Design Professional before installing on Nuts & Washers or on a Mudsill.
- C) Use 1/4"x4-1/2" USP-WS Series screws (or equal) at top connections with a 2x filler. If the top of Panel is in direct contact with the collector above (top plates, header, beam, etc.) use 1/4 x 3" (minimum)
- D) For installations with a 4x filler above 1/4" diameter screws are required at the Panel edges to brace for the out-of-plane hinge or when they are specified by the Design Professional.



- NOTES:**
- 1) SURFACE FINISHES, CONNECTORS AND FIXTURES ARE ATTACHED TO THE PANEL FACE WITH # 10 SELF-TAPPING SCREWS SPACED NO LESS THAN 2-1/4" OC.
  - 2) ATTACHMENTS TO THE PANEL EDGES ARE MADE WITH # 12 SELF-TAPPING SCREWS.
  - 3) STRUCTURAL CONNECTIONS ARE TO BE DESIGNED BY THE DESIGN PROFESSIONAL.
  - 4) STRUCTURAL HARDWARE USED TO TRANSFER LOADS SHOULD NOT EXCEED 12 GAGE.

REVISIONS DATE

**FRAMING DETAILS - HFX PANELS**

THIS DETAIL SHEET IS NOT PROPRIETARY AND IS NOT REQUIRED FOR PLAN SUBMITTAL WITH HARDY FRAME PRODUCTS

**HARDY FRAME**  
SHEAR WALL SYSTEM  
1732 PALMA DRIVE, SUITE 200, VENTURA, CA 93003  
TELEPHONE: 800 754-3030 / www.hardyframe.com



DATE:  
1-1-2016

**HFX2**

D