

Application for Design Review by the County Coastside Design Review Committee

County Government Center • 455 County Center • Redwood City CA 94063

Mail Drop PLN 122 • 650 · 363 · 4161 • FAX 650 · 363 · 4849

Permit #: PLN

Other Permit #: WA

Applicant:	Owner (if different from Applicant):
Name: Scott Yamamoto	Name: Lywe
Address: 951 Malaga St.	Address:
Half Moon Bay Zip: 94019	Zip:
Phone, W: 6502704446 H: 650270	4446 Phone, W: H:
Email: yamamotos1@gmail.com	Email:
Architect or Designer (if different from Name: Landmark Designs -Krista Brass	
Address: 2378 Huntington Dr., Aptos, Ca	A Zip:
Phone, W: 4087611218 H: 831331	0432 Email: landmarkdesigns@gmail.com
APN: 047293330 Address: 951 Malaga Street EL Granada, CA Zip: 94,019	Existing Development (Please describe): 560 S/F single Family Home TB Demolished
EL Granada, CA Zip: 94,019 Zoning:R1	560 S/F single Family Home
Parcel/lot size: 6000	sq. ft.
Project:	Additional Permits Required:
New Single Family Residence: $2,2$	78.4 sq. ft Certificate of Compliance Type A or Type B
Addition to Residence:	sq. ft Coastal Development Permit
Other:	Fence Height Exception (not permitted on coast)
	Grading Permit or Exemption
Describe Project:	☐ Home Improvement Exception
New Construction single	Family Non-Conforming Use Comil
Two Story Home,	 Off-Street Parking Exception
1 -1	JUL 0 9 2015

San Mateo County Planning and Building Department

San Mateo County

Planning and Building Department

Certificate of Exemption or Exclusion from a Coastal **Development Permit**

Permit #: PLN 20 15-2 Permit #: BLD __

455 County Center, 2nd Floor • Redwood City, CA • 94063 Mail Drop: PLN 122 • TEL (650) 363-4161 • FAX (650) 363-4849

Permanent Record Microfilming Required

f. :eselmometton	
Owner Name: SCOTT YAMA MOTO Address: 951 MALAGA STREET ELGRANADA, CA Zip: Phone, W: H: 650.270.444	Applicant Name: MIKE MCCARTHY Address: 122 SAVATOGA AVE. SUITE 100 SANTA CLASSA 95051 Phone, W: (408) 747.9420
Email Address: Yamamoto S 1 @gmay	
Project Description: DEMA (E) 560 S.F. HOME BULLD (N) 2. STORY SINGLE FAMILY HOME OF 2,2785.F. Assessor's Parcel Number(s): 047 -293- 330	Existing water source: Utility connection P.U.C. EL GRANADA, DISTRETANDA DIST
basis for exemption or exclusion are true and correct to the be in accordance with the terms of the exemption/exclusion cate exemption or exclusion issued for a water well and/or storage event the future house, the well, and/or storage tank requires	is for this exemption or exclusion. The information herein and the est of our knowledge and we hereby agree to carry out this project igory selected on reverse. We also understand and agree that any tank in the single family exclusion area will be invalidated in the avariance. The single family exclusion area will be invalidated in the avariance.
Owner Date	Applicant Date

Both Owner and Applicant must sign unless this Application for Exemption or Exclusion accompanies a Building Permit Application for which the Applicant is an agent for the Owner acceptable to the Building Inspection Section.

Environmental Information Disclosure Form

PLN 2013-27-8
BLD_

Projec	t Addres	s: 951 MALAGA STREET	Name of Owner: SCOTT YAMAMOTO Address: - SAME - GEO 270 444
Assess	sor's Par	cel No. 047 _ 293 _ 330	Phore: MIKE MCCARTH Name of Applicant: Scott YAMAMOTO)
Zoning	District:	PISIT	Phone: 408 • 747.9420
Parcel Describ purposi creeks,	size: pe the ext e of any e vegetation	easements on the parcel and a description of	ises on the project parcel, including the existence and any natural features on the project parcel (i.e. steep terrain, SINENCE, WILD NEW TWO STURY
SHAR DON'T PLANTED		Environmental Quality Act (CEQA) F	Review
Yes	No	Will this project involve:	
	V	a. Addition to an existing structure > 50% o	f the existing area OR > 2,500 sq. ft?
	V	b. Construction of a new multi-family reside	
	V	c. Construction of a commercial structure >	
		 d. Removal of mature tree(s) (≥ 6" d.b.h. in residential zoning district)? If yes, how many trees to be removed? 	Emerald Lake Hills area or ≥ 12" d.b.h. in any
V		e. Land clearing or grading? If yes, please state amount in cubic yards Excavation: 40 c.y.	s (c.y.): Fill: 20 c.y.
	<u> </u>	f. Subdivision of land into 5 or more parcels	9?
	/	g. Construction within a State or County sce	
		h. Construction within a sensitive habitat?	
		i. Construction within a hazard area (i.e. sei	
		J. Construction on a hazardous waste site (c	check with Co. Env. Health Division)?
Please		all "Yes" answers:	
	E	F.F. LOV	BL IS ONE LEVEL,
		OT IS FAIRLY LEVEL!	

Staff Use Only

4. Basis of Exemption or Exclusion

Use attached review sheet to determine basis of exemption and whether project qualifies. Review basis of exemption with applicant/owner and initial appropriate category below:

Initial A. Improvements to Existing Single Family Residence [PRC 30610(a), CCAG 13250, ZR 6328.5(a)] B. Improvements to Existing Structure Other Than Single Family Residence or Public Works Facility. [PRC 30610(b), CCAG 13253, ZR 6328.5(b)] C. Existing Navigation Channel. [PRC 30610(c). ZR 6328.5(c)] D. Repair or Maintenance Activity. [PRC 30610(d), CCAG 13252, ZR 6328.5(d)] E. Single Family Residence Categorical Exclusion Area. [PRC 30610(e), CCAG 13240, AB 643, ZR 6328.5(e)] Required	F. Agriculturally-Related Development Categorical Exclusive Area. [PRC 30610(e), CCAG 13240, ORDERS E-79-7
Inspection made by: Yes No Removal of trees? If Yes, is tree removal permit included? Trimming of trees? Excessive removal of vegetation? Excessive grading? (If Yes, CDP is required) Erosion control plan required?	Approval of Permit is subject to the following: (check if applicable) Submittal and Approval of a Tree Removal Permit Submittal and Approval of a Grading Permit Submittal and Approval of an Erosion Control Plan Submittal and Approval of a Coastal Dev. Permit
I have reviewed the above-described project and have determ checked above. Exemption/Exclusion is approved. Planning Department Project is subject to the following condition(s) of approval:	nined that it meets all criteria for the exemption/exclusion Date
 Fee collected Original Certificate of Exemption to Building Inspection file. Copies of Certificate of Exemption to: Applicant/Owner. Planning Department Exemption Binder. 	3. Any relevant Planning or Building Inspection files. 4. California Coastal Commission, 45 Fremont Street, Suite 2000, San Francisco, CA 94105Update Permit*Plan Case Screen and Activities

Yes	No	Will the project involve:
V		a. Construction of side of the of the of an existing, legal structure?
HOLE THE SECOND STATES	/	b. Exterior construction within 100-feet of a stream?
	/	c. Construction, maintenance or use of a road, bridge, or trail on a stream bank or unstable hill slope
	V	d. Land-use within a riparian area?
ø	/	e. Jimber harvesting, mining, grazing or grading?
	V,	f. Any work inside of a stream, riparian corridor, or shoreline?
	·V.	g. Release or capture of fish or commerce dealing with fish?
lease		any "Yes" answers:
	• . • .	
		·

3. Na	tional	Pollutant Discharge Elimination System (NPDES) Review
Yes	No	Will the project involve:
	1	a. A subdivision or Commercial / Industrial Development that will result in the addition or replacement o 10,000 sq. ft. or more of impervious surface?
	/	If yes, Property Owner may be required to implement appropriate source control and site design measures and to design and implement stormwater treatment measures, to reduce the discharge of stormwater pollutants. Please consult the Current Planning Section for necessary forms and both construction and post-construction requirements.
	1	b. Land disturbance of 1 acre or more of area?
	V	If yes, Property Owner must file a Notice of Intent (NOI) to be covered under the statewide General Construction Activities Storm Water Permit (General Permit) prior to the commencement of construction activity. Proof of coverage under State permit must be demonstrated prior to the issuance of a building permit.

I hereby certify that the statements furnished above and in the attached exhibits present the data and information required for this initial evaluation to the best of my ability, and the facts, statements and information presented are true and correct to the best of my knowledge and belief. If any of the facts represented here change, it is my responsibility to inform the County.

Signed:

Applicant may sign


Date:

7-9-15

RECEIVED

NOV 1 8 2015

San Mateo County Planning and Building Department




YAMAMOTO RESIDENCE

PLN 2015 - 00278



1 REVISIONS 11/16/15 C.C./P.D.



A NEW HOME

~for~

THE YAMAMOTO FAMILY


951 MALAGA STREET

EL GRANADA, CA 94019

INDEX

- A-1 COVER SHEET, SITE PLAN, INDEX, VICINITY MAP CROSS SECTION A
- SU-1 TOPOGRAPHIC SURVEY
- LS-1.1 LANDSCAPE PLAN

 LS-1.2 IRRIGATION PLAN
 - A-2 FIRST FLOOR PLAN, SECOND FLOOR PLAN
 - A-3 FRONT, REAR & SIDE ELEVATIONS
 - A-4 ROOF PLAN
 - C-1 GRADING, DRAINAGE, EROSION CONTROL PLAN
 - BMP BEST MANAGEMENT PRACTICES, WATER POLLUTION PREVENTION PROGRAM



PROJECT INFORMATION

SCOPE OF WORK: DEMOLISH (E) HOME AND REPLACE W/ A NEW SINGLE FAMILY, TWO STORY HOME WITH 3-BEDROOMS AND 2 1/2 BATHS INCLUDING 2- CAR GARAGE AND UNCONDITIONED LAUNDRY ROOM

<u>APN:</u> 047293330 <u>ADDRESS:</u> 951 MALAGA STREET, EL GRANADA, CA, 94019-3141 <u>LOT SIZE (SQ. FT.):</u> 6000 <u>YEAR BUILT:</u> 1931 <u>ZONING:</u> R-1/S-17/DR/CD

EXISTING S.F.: 560

 NEW FIRST FLOOR:
 949.6
 S.F.

 NEW SECOND FLOOR:
 1,328.8
 S.F.

 TOTAL:
 2,278.4
 S.F.

NEW 2- CAR GARAGE: 490 S.F.

NEW UNCONDITIONED LAUNDRY ROOM: 131.4 S.F.

ROOF COVERAGE: 1,408.5 S.F. (620.5 +438+350) ROOF DECK COVERAGE MAXIMUM: 1,408.5 X .20 (20 %) = 281.7 MAX.


ROOF DECK: 131.4 (7.3X18)+140 (7X20)=271.< 281.7

F.A.R. MAXIMUM: 6,000 x .45 = 2,700 S.F

LOT COVERAGE S.F.: 1,582.5 < 2,700

VICINITY MAP

PARCEL MAP



REVISIONS BY

11/16/15 C.C./
P.D.

COVER SHEET,
SITE PLAN
INDEX,
PROJECT DESCR.
VICINITY MAP

THE YAMAMOTO FAMILY
951 MALAGA STREET

ANDMARK PESIGNS

DESIGN • DEVELOPMENT

CONSTRUCTION MAIN GENERAL PERSIEFVATION

www.landmarkdesigns.net

B

DRAWN BY:
K.B.


CHECKED BY:
S.Y.

DATE
NOV. 16, 2015

SCALE
AS SHOWN

JOB NO.

A1




ZONE A: DRIP IRRIGATION, REGULAR WATER

ZONE B: DRIP IRRIGATION, MODERATE WATER

ZONE C: DRIP IRRIGATION, LITTLE WATER

ZONE D: SPRAY IRRIGATION, MODERATE WATER



IRRIGATION NOTES

GENERAL.

CONTRACTOR QUALIFICATIONS: THE SYSTEM SHALL BE INSTALLED BY AN EXPERIENCED FIRM. REGULARLY ENGAGED IN IRRIGATION INSTALLATION. CONTRACTOR SHALL HAVE A MINIMUM OF THREE YEARS OF SUCCESSFUL EXPERIENCE WITH INSTALLATIONS.

PROTECTION: THE IRRIGATION CONTRACTOR SHALL PROTECT ALL MATERIALS AND WORK AGAINST INJURY FROM ANY CAUSE AND SHALL PROVIDE AND MAINTAIN ALL NECESSARY SAFEGUARDS FOR THE PROTECTION OF THE PUBLIC. S/HE SHALL REPAIR ANY DAMAGE CAUSED BY, OR DURING THE PERFORMANCE OF HIS WORK AT NO ADDITIONAL COST TO THE OWNER. THE IRRIGATION CONTRACTOR SHALL EXERCISE CARE IN DIGGING AND OTHER WORK SO AS NOT TO DAMAGE EXISTING WORK, INCLUDING UNDERGROUND CABLES AND PIPES. SHOULD SUCH OVERHEAD OR UNDERGROUND OBSTRUCTIONS BE ENCOUNTERED THAT INTERFERE WITH HIS WORK, THE OWNER SHALL BE CONSULTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMMEDIATE REPAIR OF ANY DAMAGE CAUSED BY HIS WORK. THIS ALSO APPLIES TO LAWN AREAS. DO NOT STORE PVC PIPE IN DIRECT SUNLIGHT. BEDS ON WHICH PIPE IS STORED MUST EXTEND FULL LENGTH OF PIPE.

3. SUBMITTALS:

- A. AS-BUILT DRAWINGS DURING THE COURSE OF THE INSTALLATION, THE IRRIGATION CONTRACTOR SHALL RECORD ALL CHANGES MADE TO THE IRRIGATION SYSTEM DURING INSTALLATION. CHANGES SHALL BE CAREFULLY DRAWN IN RED LINE ON A PRINT OF THE IRRIGATION SYSTEM DRAWING. UPON COMPLETION OF THE INSTALLATION, THIS RED LINE DRAWING SHALL BE GIVEN TO THE OWNER FOR USE AS AN AS-BUILT DRAWING.
- B. MANAGEMENT INSTRUCTIONS AFTER THE IRRIGATION SYSTEM IS INSTALLED AN APPROVED, THE OWNER SHALL BE INSTRUCTED IN THE COMPLETE OPERATION AND MAINTENANCE OF THE SYSTEM BY THE CONTRACTOR. THE CONTRACTOR SHALL FURNISH TWO COPIES OF AN IRRIGATION SYSTEM MANAGEMENT MANUAL PREPARED BY THE SYSTEM INSTALLER.
- SCOPE OF WORK: THE CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT FOR A COMPLETE OPERATING UNDERGROUND IRRIGATION SYSTEM AS SPECIFIED HEREIN AND AS SHOWN ON THE DRAWINGS. WORK AND MATERIALS SHALL CONFORM TO ALL CURRENT STATE AND LOCAL LAWS, RULES, CODES OR REGULATIONS AS MAY BE APPLICABLE TO THIS WORK.
- GUARANTY: MATERIALS, EQUIPMENT, AND WORKMANSHIP FURNISHED UNDER THIS CONTRACT SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE. THE GUARANTY SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:
- A. FILLING AND REPAIRING DEPRESSIONS AND REPLACING PLANTINGS DUE TO SETTLEMENT OF IRRIGATION TRENCHES.
- B. ENSURING THAT THE IRRIGATION SYSTEM HAS BEEN ADJUSTED TO SUPPLY PROPER WATER COVERAGE OF AREAS DESIGNED TO RECEIVE WATER.

MATERIALS.

- 1. PVC PIPE: BELOW-GROUND PIPE SHALL BE SCHEDULE 40 OR CLASS 200.
- 2. PIPE ABOVE GRADE: COPPER PIPE
- 3. PVC FITTINGS: ALL PVC FITTINGS SHALL BE SCHEDULE 40, TYPE 1, NSF APPROVED UNLESS OTHERWISE
- 4. PVC SLEEVES: ALL CROSSINGS UNDER PAVED AREAS FOR WATER LINE AND WIRE RUNS SHALL BE SCHEDULE 40 PVC.
- AUTOMATIC CONTROL VALVE: BRASS BODY OR AS APPROVED BY LANDSCAPE ARCHITECT.
- 6. DRAIN VALVES: SHALL BE OF A GLOBE CONFIGURATION AND CONSTRUCTED OF BRASS WITH A RUBBERIZED SEAT.
- 7. CONTROL WIRE: SOLID COPPER, 24 VOLT, PLASTIC INSULATED, UF DIRECT BURIAL WIRE, SIZE #14. COMMON GROUND WIRE SHALL BE WHITE. CONTROL WIRE SHALL BE COLOR OTHER THAN WHITE. PROVIDE SPARE CONTROL WIRE OF A DIFFERENT COLOR ALONG THE LENGTH OF THE MAINLINE.

CONTROLLER.

1. CONTROLLER SHALL BE A SELF-ADJUSTING CONTROLLER WITH WEATHER TRACKING SYSTEM. 2. CONTROLLER LOCATION: MOUNT CONTROLLER ON OUTSIDE OF HOUSE ON NORTH SIDE. CENTER CONTROLLER AT 4 - 6" FROM FINISH GRADE.

INSTALLATION.


- 1. PRIOR TO COMMENCING CONSTRUCTION, VERIFY WATER PRESSURE AT POINT OF CONNECTION AND CONFIRM LOCATION OF ALL EXISTING SUBSURFACE UTILITIES.
- 2. TRENCHING AND BACKFILLING: CONTRACTOR SHALL EXERCISE CAUTION WHEN WORKING NEAR EXISTING UTILITIES AND STRUCTURES. TRENCHES SHALL BE EXCAVATED TO THE REQUIRED DEPTHS FOR PIPE INSTALLATION, AND SHALL BE STRAIGHT AND UNIFORM. BACKFILL MATERIAL SHALL BE SOIL FREE OF ROCK, GRAVEL LARGER THAN 2", ORGANIC MATERIAL, OR DEBRIS. BACKFILL SHALL BE COMPACTED BY UNIFORMLY TAMPING IN LOOSE LIFT THICKNESSES OF 8" TO A DENSITY APPROXIMATELY EQUAL TO THE ADJACENT UNDISTURBED SOIL.
- 3. INSTALLATION OF PLASTIC: PIPE SHALL BE SNAKED FROM ONE SIDE TO THE OTHER IN TRENCHES TO ALLOW FOR EXPANSION AND CONTRACTION. PIPE SHALL BE INSTALLED UNDER DRIVEWAYS OR PARKING AREAS IN SCHEDULE 40 SLEEVES AT LEAST 12" BELOW FINISH GRADE, 18" FOR MAINLINE PIPE. PIPE SLEEVES SHALL BE 2X THE DIAMETER OR SUM OF DIAMETERS OF PIPES BEING SLEEVED AND SHALL EXTEND MIN. 12" BEYOND EDGE OF PAVING, WALL, OR STRUCTURE BEING SLEEVED THROUGH. PARALLEL PIPES MAY BE INSTALLED IN A COMMON TRENCH. PROVIDE MINIMUM SEPARATION OF 3". DO NOT INSTALL PIPES DIRECTLY ABOVE ONE ANOTHER.

- 4. POP-UP SPRINKLER HEADS: SET SPRINKLER HEADS PERPENDICULAR TO FINISH GRADE. SET SPRINKLER HEADS ADJACENT TO EXISTING WALKS, CURBS, AND OTHER PAVED AREAS TO GRADE. SET SPRINKLER HEADS INSTALLED IN LAWN AREAS WHERE TURF HAS NOT YET BEEN ESTABLISHED, 4" ABOVE PROPOSED FINISH GRADE. ADJUST HEADS TO PROPER GRADE WHEN TURN IS SUFFICIENTLY ESTABLISHED OR WHEN TURF CAN BE WALKED ON WITH APPRECIABLE HARM. SUCH LOWERING OR RAISING OF HEADS SHALL BE PART OF THE ORIGINAL CONTRACT WITH NO ADDITIONAL COST TO OWNER. ADJUST SPRINKLER HEAD PATTERN AND RADIUS FOR PROPER DISTRIBUTION AND COVERAGE.
- 5. AUTOMATIC CONTROL VALVES: IN A VALVE BOX POSITIONED OVER THE VALVE SO THAT ALL PARTS OF THE VALVE CAN BE REACHED FOR SERVICE.
- 6. VALVE BOXES: SHALL BE CARSON-BROOKS, OR EQUAL. HEAVY DUTY PLASTIC BOX WITH BOLT-DOWN DROP-IN COVER AND HEX HEAD BOLTS. COVER MARKING: IRRIGATION CONTROL VALVE. COLOR: BLACK, BOXES SHALL BE SET FLUSH WITH FINISH GRADE. VALVE BOXES SHALL BE 12" X 17" X 12" DEEP.
- 7. CONTROL WIRE: PLACE THE CONTROL WIRE BELOW THE PIPE FOR PROTECTION OF THE WIRE. USE WATERPROOF WIRE CONNECTORS AT ALL SPLICES. SPLICING OF 24V WIRES IS PERMITTED ONLY IN VALVE BOXES. TAPE WIRES TOGETHER EVERY 10 FEET. TAPING WIRES NOT REQUIRED IN SLEEVES WIRE SHALL BE PLACED LOOSELY IN THE TRENCHES TO ALLOW FOR CONTRACTION. A 1-FOOT LOOP OF WIRE SHALL BE COSTRUCTED AT ALL CORNERS FOR FUTURE REPAIR. LOOP 24" EXCESS WIRE INTO ONE VALVE BOX AT EACH GROUPING.

DRIP IRRIGATION.

- 1. GENERAL: DRIP IRRIGATION TUBING AND EMITTERS SHALL BE INSTALLED ONLY AFTER PLANTING AND FINISH GRADING IS COMPLETE, WATERING WELLS ARE INSTALLED.
- 2. FLUSH DRIP IRRIGATION VALVE ASSEMBLY PRIOR TO INSTALLING PIPE. FLUSH SOLID WALL PVC PIPE PRIOR TO INSTALLING DRIP IRRIGATION TUBING. PROVIDE EMACULATE CONNECTIONS AT ALL TIMES TO PREVENT PARTICLES FROM CLOGGING TUBING AND EMITTERS.
- 3. TUBING UNDER PAVEMENT OR PATHWAYS SHALL BE INSTALLED IN RIGID PIPE SLEEVES, MINIMUM 6" BELOW FINISHED GRADE.
- 4. FILTER: FLUSHABLE WYE FILTER SHALL HAVE A MINIMUM OF 200 MESH SCREEN.
- 5. PRESSURE REDUCER: IF WATER PRESSURE AFTER FILTER EXCEEDS 25 PSI, PROVIDE PRESSURE REDUCER SET TO 25 PSI.


- 6. TUBING AND EMITTERS: DRIP TUBING SHALL BE LAID ON THE FINISHED GRADE AND STAKED AT 3' - 0" O.C. WITH DRIP TUBING STAKES, DO NOT PINCH TUBING WITH STAKES. PROVIDE FLUSH VALVE AT END OF EACH LINE. EMITTERS SHALL BE INSTALLED WITH BARBED CONNECTORS AND PLACED ABOVE ROOT ZONE OF PLANT, BUT NOT AGAIST
- TRUNK OR STEM, AS FOLLOWS: NINE - 1 GPH EMITTERS SIX - 1 GPH EMITTERS
- B. 5 GAL SHRUBS: C. 1 GAL PERENNIALS: D. FLATSTOCK:
- THREE 1 GPH EMITTER RAINBIRD DRIPLINE OR MICROSPRAY 7. DRIP IRRIGATION VALVES SHALL INITIALLY RUN 1 HOUR DAILY, BEGINNING AT 5:00AM,
- AND SHALL BE ADJUSTED TO ENSURE COMPLETE IRRIGATION OF PLANTINGS. SITE CLEAN-UP.
- 1. CLEANING: CONTRACTOR SHALL AT ALL TIMES, KEEP THE PREMISES, INCLUDING THE PAVED AREAS, FREE FROM ACCUMULATIONS OF WASTE CAUSED BY HIS EMPLOYEES OR WORK. REMOVE ALL SURPLUS MATERIAL AND DEBRIS FROM THE SITE UPON COMPLETION OF THE WORK.
- 2. CONTRACTOR SHALL SCHEDULE A FINAL WALK THROUGH WITH CLIENT.
- CONTRACTOR SHALL GUARANTY IRRIGATION FOR 30 DAYS BEYOND FINAL WALK THROUGH. IF IRRIGATION LINES LEAK OR SYSTEM FAILS DUE TO IMPROPER INSTALLATION PRACTICES, CONTRACTOR SHALL REPAIR IRRIGATION.




IRRIGATION PLAN

REVISIONS









ZA

Date 4 Nov. 2015 Scale 1/4 = 1 -01

Drawn LG JOB YAMAMOTO





271.4 < 281.7 (20% OF (E) ROOF)

REVISIONS BY

11/16/15 C.C./
P.D.

FIRST FLOOR PLAN SECOND FLOOR PLAN

E YAMAMOTO FAMILY

951 MALAGA STREET

DESIGN • DEVELORMENT
CONSTRUCTION MANAGEMENT • PPERSERVATION
WWW.landmarkdesigns.net

P.O. BOX 2221 LOS GATOS, CA 95051 408-761-1218

DRAWN BY:
K.B.

CHECKED BY:
S.Y.


DATE
NOV. 16, 2015


SCALE
1/4"=1'0"

JOB NO.

SHEET

A2





1/4" = 1'0"

ROOF PLAN

ROOF PLAN DESIGN • DEVELOPMENT


CONSTRUCTION MANAGEMENT • PPERSERVATION

WWW.landmarkdesigns.net

P.O. BOX 2221 LOS GATOS, CA. 95031

408-761-1218

	DRAWN BY
	K.B.
	CHECKED I
	S.Y.
	DATE
	NOV. 16,
N.	SCALE
	1/4"=1'0
	JOB NO
	SHEET






Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Water Pollution Prevention Program

Clean Water. Healthy Community.

Materials & Waste Management



Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ☐ Use (but don't overuse) reclaimed water for dust control.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control




Maintenance and Parking

- ☐ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ☐ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- ☐ Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- □ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

Earthmoving




- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- □ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.Abandoned wells
- Buried barrels, debris, or trash

Paving/Asphalt Work




- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- Collect and recycle or appropriately dispose of excess abrasive gravel or sand.
 Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement.

Sawcutting & Asphalt/Concrete Removal


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.

Concrete, Grout & Mortar Application




- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

Landscaping



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

Painting & Paint Removal




Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer.


 Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.

Dewatering



- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.

Storm drain polluters may be liable for fines of up to \$10,000 per day!



SCHEMATIC PLANT LIST

IRUBS			
LATIN NAME	COMMON NAME	NATIVE	WATER USE
ARBUTUS UNEDO 'ELFIN KING'	STRAWBERRY BUSH	Х	LOW
BAMBUSA MULTIPLEX 'ALPHONSE KARR'	ALPHONSE KARR BAMBOO		LOW
CARISSA MACROCARPA	NATAL PLUM	Х	LOW
CITRUS 'IMPROVED MEYER' SHRUB FORM	MEYER LEMON		REGULAR
COPROSMA 'MARBLE QUEEN'	MIRROR PLANT		LOW
CORREA REFLEXA 'CARPENTER ROCKS'	AUSTRALIAN FUSCHIA		LOW
ESCALLONIA 'COMPAKTA'	ESCALLONIA		MODERATE
HEBE ANDERSONII 'VARIEGATA'	HEBE		REGULAR
LAVANDULA ANGUSTIFOLIA 'HIDCOTE'	ENGLISH LAVENDER		MODERATE
PHYLOSTACHYS NIGRA (IN BAMBOO BARRIER)	BLACK BAMBOO		LOW
PITTOSPORUM TOBIRA 'VARIEGATA'	PITTOSPORUM		MODERATE
ROSMARINUS OFFICINALIS 'BARBECUE'	ROSEMARY		LOW
SARCOCOCCA RUSCIFOLIA	FRAGRANT SARCOCOCCA		MODERATE

EKENNIALS			
LATIN NAME	COMMON NAME	NATIVE	WATER USE
ACHILLEA MILLEFOLIUM 'STRAWBERRY SEDUCTION'	YARROW	Х	LOW
ARGYRANTHEMUM FRUTESCENS 'SILVER LADY'	MARGUERITE DAISY		LOW
CAREX DIVULSA	BERKELEY SEDGE		LOW
ECHIUM CANDICANS	PRIDE-OF-MADEIRA	Х	LOW
LIMONIUM PEREZII	STATICE		MODERATE
PENNISETUM ORIENTALE 'KARLEY ROSE'	FOUNTAIN GRASS		MODERATE
TULBAGHIA VIOLACEA	SOCIETY GARLIC		MODERATE
WOODWARDIA FIMBRIATA	GIANT CHAIN FERN	X	MODERATE

GROUND COVER

LATIN NAME	COMMON NAME	NATIVE	WATER USE
AGROSTIS PALLENS SOD	NATIVE BENTGRASS LAWN	Х	LOW
ARMERIA MARITIMA	SEA PINK	Х	LOW
COTYLEDON ORBICULATA 'PIG'S EAR'	COTYLEDON		LOW
DYMONDIA MARGARETAE	DYMONDIA		MODERATE
ECHEVERIA ELEGANS	HEN AND CHICKS		MODERATE
ERIGERON GLAUCUS 'CAPE SEBASTIAN'	SEASIDE DAISY	X	LOW
SEDUM RUPESTRE 'ANGELINE'	STONECROP	\	LOW

JAPANESE ENTRY GARDEN

LATIN NAME	COMMON NAME	NATIVE	WATER USE
FAMILY JAPANESE MAPLE FROM POT	JAPANESE MAPLE		REGULAR
HAKONECHLOA MACRA 'AUREOLA'	JAPANESE FOREST GRASS		REGULAR




SCHEMATIC LANDSCAPE PLAN









Scale 1/4 = 1 - 01

JOD YAMAMOTO

Drawn LG

YAMAMOTO RESIDENCE 951 MALAGA STREET, EL GRANADA,